

15005 RAMAH CHURCH RD

1/4/2008

duponbj

Groundwater and Wastewater Services File Imaging Project
May 2007
Barcode Font = IDAutomationHC39M

AC

FEE: _____ **AUTHORIZATION FOR WASTEWATER SYSTEM CONSTRUCTION**
DATE: _____ **VOID SIXTY (60) MONTHS FROM DATE OF ISSUANCE**

DATE: 5/18/2000 PERMIT NO: 4291B
PARCEL NO: 011261 21
JOB LOCATION ADDRESS: 15015 Ramah Church Rd
PROPERTY OWNER: Jeff Burton
BUILDING CONTRACTOR: -
SUBDIVISION NAME: NA
AUTHORIZATION ISSUED BY: Phil A. Walker RS. DATE: 5/18/2000
DEHNR AUTHORIZED AGENT

AUTHORIZATION CONDITIONS

1. WASTEWATER SYSTEM CONSTRUCTION AND INSTALLATION MUST MEET ALL CONDITIONS AND SPECIFICATIONS AS SET FORTH IN IMPROVEMENT PERMIT NO. 4291B, AND THE ATTACHED SITE PLAN WITH SYSTEM DETAILS. CONSTRUCTION AND INSTALLATION MUST ALSO MEET ALL REQUIREMENTS SET FORTH IN THE RULES GOVERNING SANITARY SEWAGE COLLECTION, TREATMENT, AND DISPOSAL AND ANY OTHER APPLICABLE RULES AND LAWS.

2. AN INSTALLATION, CONSTRUCTION, ALTERATION AND/OR REPAIR APPROVAL MUST BE SECURED PRIOR TO INSTALLATION OF THE SEPTIC TANK SYSTEM. THE INSTALLER OF THE SYSTEM SHALL BE A REGISTERED SEPTIC TANK CONTRACTOR WITH MECKLENBURG COUNTY HEALTH DEPARTMENT.

3. ANY ALTERATION IN SITE OR SOIL CONDITIONS (INCLUDING LOCATION OF STRUCTURES AND APPURTENANCES) OR MODIFICATION IN USE, DESIGN WASTEWATER FLOW, OR WASTEWATER CHARACTERISTICS AS SPECIFIED IN THE ASSOCIATED IMPROVEMENT PERMIT AND APPLICATION, MAY SUBJECT THIS AUTHORIZATION AND ASSOCIATED PERMIT(S) TO REVOCATION.

4. OTHER CONDITIONS: _____

OWNER CERTIFICATION

I CERTIFY THAT THERE HAVE BEEN NO ALTERATIONS IN SITE OR SOIL CONDITIONS OR MODIFICATIONS TO FACILITY, WASTEWATER FLOW, OR WASTEWATER CHARACTERISTICS FROM THOSE SPECIFIED IN THE ORIGINAL APPLICATION OR ASSOCIATED IMPROVEMENT PERMIT UNLESS AUTHORIZED IN WRITING BY THE MECKLENBURG COUNTY HEALTH DEPARTMENT. I ALSO UNDERSTAND THAT ANY SUCH ALTERATIONS, MODIFICATIONS, OR FALSE INFORMATION ARE GROUNDS FOR REVOCATION OF PERMITS AND AUTHORIZATION TO CONSTRUCT.

X _____ 5-18-00
SIGNATURE OF OWNER/OWNER'S REPRESENTATIVE DATE

CONDITIONS OF IMPROVEMENT PERMIT

Permit Number: 4291B

Tax Number: 011 261 21

The IMPROVEMENT PERMIT is subject to revocation if site plans or the intended use change. There is to be NO grading, filling or disturbance of the soil in the area of the septic tank system or repair area.

CONSTRUCTION AUTHORIZATION must be obtained prior to receiving a Building Permit. The Construction Authorization is NOT transferable. Do not clear, grade, fill or disturb soil prior to obtaining a Construction Authorization.

Domestic-type wastewater only. No industrial process wastewater may be discharged into the system.

Basement	___ Yes	~~✓~~ No ~~sink~~ plw	✓ Partial Basement

Type Primary Wastewater System Type (circle one): I II (III) IV V VI	✓ Conventional	___ Low Pressure Pipe	___ Innovative or Experimental:
	___ Prefabricated, permeable block panel system	___ Large Diameter Pipe	___ IWWS-93-1
		___ Fill	___ IWWS-93-2
	___ Shallow Placed Conventional	___ Other	___ IWWS-94-1

3 Long-term acceptance rate	720 Max gallons/day wastewater flow	2160 Absorption Area (sq ft)	9' Trench spacing (min. on centers)
yes Serviced by private well	1500 Gallon septic tank	800' Total trench length (ft)	24" Maximum trench depth (At least 12" of provisionally suitable soil must remain between trench bottom and unsuitable soil conditions)
6 Bedrooms in residence ~~3~~ plw	1000 Gallon pump tank	12" Depth of stone	

Any surface waters present: NO Type: Minimum separation distance:

Site modifications required:

Additional Conditions: Keep the septic system > 100' from the existing well
Keep the septic system > 15' from the basement

Repair Area System Type Type (circle one): I II (III) IV V VI	✓ Conventional	___ Low Pressure Pipe	___ Innovative or Experimental:
	___ Prefabricated, permeable block panel system	___ Large Diameter Pipe	___ IWWS-93-1
		___ Fill	___ IWWS-93-2
	___ Shallow Placed Conventional	___ Other	___ IWWS-94-1

2160' Absorption Area (Sq ft) 800' Total Trench Length (Ft)	12" Depth of Stone Trench	9' Trench spacing (min. on centers)	24" Maximum Trench Depth

For existing system, enter the year originally installed:

The undersigned, an authorized agent of the MECKLENBURG COUNTY HEALTH DEPARTMENT, certifies that the Department has approved the Request for the Job Location contained in this document. This approval is granted in accordance with the provisions of Laws and Rules For Sewage, Treatment and Disposal in effect at the time of issuance of the permit and is subject to the following provisions:

- No work shall be conducted on the septic tank system until an Installation, Construction, Alteration and/or Repair Approval is granted by this Department.
- This Improvement permit is transferable.

Philip S. Walker RS. — DEHNR Authorized Agent — Date


x [signature] — Owner/Agent Signature — Date 5/18/00

MECKLENBURG COUNTY
HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
c/o HAL MARSHALL CTR.
SUITE 211
700 N. TRYON ST.
CHARLOTTE, N.C. 28202.
(704) 336-5102

NORTH CAROLINA DEPARTMENT OF
ENVIRONMENTAL, HEALTH,
AND NATURAL RESOURCES
DIVISION OF ENVIRONMENTAL HEALTH
ON-SITE WASTEWATER SECTION

4294B

11-07



COMMENTS

6 Bedroom Residence
1500 ST Lift/sewg
1000 DT required
6 lines x 133' long
x 3' wd x 12" Stone
798 LF
Keep the septic system > 100' from the existing well
TXPE III b
Repair Area

5/18/00

TAX LINE MAP BOOK 11 PAGE 07
MECKLENBURG COUNTY, NORTH CAROLINA
REVISED 5-7-98 MG | SCALE 1" = 400'


PROPOSED PLOT PLAN

HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
700 NORTH TRYON STREET
CHARLOTTE, NC 28202
PHONE (704) 336-5102

FILE: 4291B

TC: 011-261-21

Draw in and name all roads adjoining the property. Draw in and accurately dimension the lot concerned. Accurately indicate property boundaries proposed and/or existing structures and driveways, underground utilities, and wells and springs within 100 feet of the proposed building or drainfield.



APPROVAL DATE _____

OWNER/AGENT SIGNATURE

DATE

White - Health Department's Copy Canary - E.H.S. Copy Pink - Owner's Copy

DEPARTMENT OF ENVIRONMENT, HEALTH, AND NATURAL RESOURCES
DIVISION OF ENVIRONMENTAL HEALTH
ON-SITE WASTEWATER SECTION

AC #1

Sheet: _____
Property ID: 011-261-21
Lot #: _____
File #: 4291B

SOIL/SITE EVALUATION
for ON-SITE WASTEWATER SYSTEM

OWNER: Jeff Burton APPLICANT: Danny Edwards
ADDRESS: 18 all Peninsula Club Dr. Corolla DATE EVALUATED: May 9, 2000
PROPOSED FACILITY: residence PROPOSED DESIGN FLOW (.1949) 396 PROPERTY SIZE: 1.0 ac
LOCATION OF SITE: 15015 Ramah Church Road PROPERTY RECORDED: _____
WATER SUPPLY: ☑Private ☐Public ☐Well ☐Spring ☐Other _____
EVALUATION METHOD: ☑Augur Boring ☐Pit ☐Cut
TYPE OF WASTEWATER: ☐Sewage ☐Industrial Process ☐Mixed

PROFILE #	3 lines 5-17-96 .1940 Landscape Position/ Slope %	Horizon Depth (IN.)	SOIL MORPHOLOGY (.1941) .1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE MINERALOGY	OTHER PROFILE FACTORS .1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	PROFILE CLASS &LTAR
1	LS	0-2"	gr/scl	Fr/SEXPl SS/SP	75" TO soil wetness	51"	N/A	None	PS .391 F_2 III
		2-51"	SBM/C	Fi/SEXPl S/P					
2	LS	0-4"	gr/scl	Fr/SEXPl SS/SP	74" TO soil wetness	46"	N/A	None	PS .391 F_2 III
		4-46"	SBM/C	Fi/SEXPl S/P					
4	LS	0-4"	gr/scl	Fr/SEXPl SS/SP	74" TO soil wetness	46"	N/A	None	PS .391 F_2 III
		4-21"	SBM/C	Fi/SEXPl S/P					
		21-46"	SBM/cl	Fr/SEXPl SS/SP					
3	LS	0-3"	gr/scl	Fr/SEXPl SS/SP	74" TO soil wetness	46"	N/A	None	PS .391 F_2 III
		3-46"	SBM/C	Fi/SEXPl S/P					
5	LS	0-3"	gr/scl	Fr/SEXPl SS/SP	74" TO soil wetness	46"	N/A	None	PS .391 F_2 III
		3-26"	SBM/C	Fi/SEXPl S/P					
		26-46"	SBM/Cl	Fr/SEXPl SS/SP					
6	LS	0-3"	gr/scl	Fr/SEXPl SS/SP	74" TO soil wetness	46"	N/A	None	PS .391 F_2 III
		3-46"	SBM/C	Fi/SEXPl S/P					
7	LS	0-3"	gr/scl	Fr/SEXPl SS/SP	74" TO soil wetness	46"	N/A	None	PS .391 F_2 III
		3-45"	SBM/C	Fi/SEXPl S/P					
		45-46"	SBM/Cl	Fr/SEXPl SS/SP					
8	LS	0-2"	gr/scl	Fr/SEXPl SS/SP	74" TO soil wetness	46"	N/A	None	PS .391 F_2 III
		2-46"	SBM/C	Fi/SEXPl S/P					

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.1945)	PS	PS
System Type(s)		
Site LTAR	.391 F_2	.391 F_2

OTHER FACTORS (.1946): _____
SITE CLASSIFICATION (.1948): Provisionally Suitable
EVALUATED BY: M.R. Mullin LSS 5-15-00
OTHER(S) PRESENT: D. Edwards

DEPARTMENT OF ENVIRONMENT, HEALTH, AND NATURAL RESOURCES
DIVISION OF ENVIRONMENTAL HEALTH
ON-SITE WASTEWATER SECTION

Sheet: 2

Property ID:

Lot #:

File #: 42918

SOIL/SITE EVALUATION
for ON-SITE WASTEWATER SYSTEM

OWNER: APPLICANT:

ADDRESS: DATE EVALUATED:

PROPOSED FACILITY: PROPOSED DESIGN FLOW (.1949) PROPERTY SIZE:

LOCATION OF SITE: PROPERTY RECORDED:

WATER SUPPLY: ☐Private ☐Public ☐Well ☐Spring ☐Other

EVALUATION METHOD: ☐Augur Boring ☐Pit ☐Cut

TYPE OF WASTEWATER: ☐Sewage ☐Industrial Process ☐Mixed

PROFILE #	.1940 Landscape Position/ Slope %	Horizon Depth (IN.)	SOIL MORPHOLOGY (.1941) .1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE MINERALOGY	OTHER PROFILE FACTORS .1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	PROFILE CLASS &LTAR
9	LS	0-3"	gr/sc1	Fr/SExP SS/SP	7YR 7/6 TO 10YR 7/1 WETNESS	46"	N/A	None	PS .39 Fr IV
		3-28"	SBK/C	Fr/SExP SP					
		28-48"	SBK/C1	Fr/SExP/SS/SC					

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.1945)		
System Type(s)		
Site LTAR		

OTHER FACTORS (.1946):

SITE CLASSIFICATION (.1948):

EVALUATED BY:

OTHER(S) PRESENT:

FILE # 42913

COMMENTS 100%

LANDSCAPE POSITION	GROUP	TEXTURE	.1955 LTAR
R-RIDGE	I	S-SAND	1.2-0.8
S-SHOULDER SLOPE		LS-LOAMY SAND	
L-LINEAR SLOPE			
FS-FOOT SLOPE	II	SL-SANDY LOAM	0.8-0.6
N-NOSE SLOPE		L-LOAM	
H-HEAD SLOPE			
CC-CONCLAVE SLOPE	III	SI-SILT	0.6-0.3
CV-CONVEX SLOPE		SICL-SILTY CLAY LOAM	
T-TERRACE		CL-CLAY LOAM	
FP-FLOOD PLAIN		SCL-SANDY CLAY LOAM	
	IV	SC-SANDY CLAY	0.4-0.1
		SIC-SILTY CLAY	
		O-ORGANIC	


CONSISTENCE	
MOIST	WET
VFR-VERY FRIABLE	NS-NON-STICKY
FR-FRIABLE	SS-SLIGHTLYSTICKY
FI-FIRM	S-STICKY
VFI-VERY FIRM	VS-VERY STICKY
EFI-EXTREMELY FIRM	NP-NON-PLASTIC
	SP-SLIGHTLYSTICKY
	P-PLASTIC
	VP-VERY PLASTIC

STRUCTURE

SG-SINGLE GRAIN
M-MASSIVE
CR-CRUMB
GR-GRANULAR
SBK-SUBANGULAR BLOCKY
ABK-ANGULAR BLOCKY
PL-PLATY
PR-PRISMATIC

MINERALOGY

SLIGHTLY EXPANSIVE
EXPANSIVE



DIVISION OF ENVIRONMENTAL HEALTH
ON-SITE WASTEWATER SECTION

#1

Sheet: _____

Property ID: 011-261-21

Lot #: _____

File #: 4291B

SOIL/SITE EVALUATION
for ON-SITE WASTEWATER SYSTEM

OWNER: Jeff Burton APPLICANT: Danny Edwards

ADDRESS: 1611 Peninsula Club Dr. Lowell DATE EVALUATED: May 9, 2000

PROPOSED FACILITY: residence PROPOSED DESIGN FLOW (.1949) 396 PROPERTY SIZE: 1.0 ac

LOCATION OF SITE: 15015 Ramah Church Road PROPERTY RECORDED: _____

WATER SUPPLY: ☑Private ☐Public ☐~~Well~~ ☐Spring ☐Other _____

EVALUATION METHOD: ☑~~Augur Boring~~ ☐Pit ☐Cut

TYPE OF WASTEWATER: ☐~~Sewage~~ ☐Industrial Process ☐Mixed

PROFILE #	1940 Landscape Position/ Slope %	Horizon Depth (IN.)	SOIL MORPHOLOGY (1941) 1941 STRUCTURE/ TEXTURE	SOIL MORPHOLOGY (1941) 1941 CONSISTENCE MINERALOGY	OTHER PROFILE FACTORS 1942 SOIL WETNESS/ COLOR	OTHER PROFILE FACTORS 1943 SOIL DEPTH	OTHER PROFILE FACTORS 1956 SAPRO CLASS	OTHER PROFILE FACTORS 1944 RESTR HORIZ	PROFILE CLASS &LTAR
1	LS	0-2"	gr/scl	Fr/SEXPl SS/SP	75" To soil wetness	51"	N/A	None	PS .391 F_2 IV
		2-51"	SBM/C	F:/SEXPl S/P					
2	LS	0-4"	gr/scl	Fr/SEXPl SS/SP	746" To soil wetness	46"	N/A	None	PS .391 F_2 IV
		4-46"	SBM/C	F:/SEXPl S/P					
4	LS	0-4"	gr/scl	Fr/SEXPl SS/SP	746" To soil wetness	46"	N/A	None	PS .391 F_2 IV
		4-27"	SBM/C	F:/SEXPl S/P					
		27-46"	SBM/cl	Fr/SEXPl SS/SP					
3	LS	0-3"	gr/scl	Fr/SEXPl SS/SP	746" To soil wetness	46"	N/A	None	PS .391 F_2 IV
		3-46"	SBM/C	F:/SEXPl S/P					
5	LS	0-3"	gr/scl	Fr/SEXPl SS/SP	746" To soil wetness	46"	N/A	None	PS .391 F_2 IV
		3-26"	SBM/C	F:/SEXPl S/P					
		26-46"	SBM/Cl	Fr/SEXPl SS/SP					
6	LS	0-3"	gr/scl	Fr/SEXPl SS/SP	746" To soil wetness	46"	N/A	None	PS .391 F_2 IV
		3-46"	SBM/C	F:/SEXPl S/P					
7	LS	0-3"	gr/scl	Fr/SEXPl SS/SP	746" To soil wetness	46"	N/A	None	PS .391 F_2 IV
		3-45"	SBM/C	F:/SEXPl S/P					
		45-46"	SBM/Cl	Fr/SEXPl SS/SP					
8	LS	0-2"	gr/scl	Fr/SEXPl SS/SP	746" To soil wetness	46"	N/A	None	PS .391 F_2 IV
		2-46"	SBM/C	F:/SEXPl S/P					

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.1945)	PS	PS
System Type(s)		
Site LTAR	.391 F_2	.391 F_2

OTHER FACTORS (.1946): _____

SITE CLASSIFICATION (.1948): Provisionally Suitable

EVALUATED BY: W.A. Marlin LSS 5-15-00

OTHER(S) PRESENT: D. Edwards

[illegible] OF ENVIRONMENT, HEALTH, AND NATURAL RESOURCES
DIVISION OF ENVIRONMENTAL HEALTH
ON-SITE WASTEWATER SECTION

Property ID:

Lot #:

File #: 4291B

SOIL/SITE EVALUATION
for ON-SITE WASTEWATER SYSTEM

OWNER: APPLICANT:

ADDRESS: DATE EVALUATED:

PROPOSED FACILITY: PROPOSED DESIGN FLOW (.1949) PROPERTY SIZE:

LOCATION OF SITE: PROPERTY RECORDED:

WATER SUPPLY: ☐Private ☐Public ☐Well ☐Spring ☐Other

EVALUATION METHOD: ☐Augur Boring ☐Pit ☐Cut

TYPE OF WASTEWATER: ☐Sewage ☐Industrial Process ☐Mixed

PROFILE #	.1940 Landscape Position/ Slope %	Horizon Depth (IN.)	SOIL MORPHOLOGY (1941) .1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE MINERALOGY	OTHER PROFILE FACTORS .1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	PROFILE CLASS &LTAR
9	LS	0-3"	gr/sCl	Fr/sEXP ss/sP	7.5YR 5/1 wetness	46"	N/A	None	PS .39 Fx IV
		3-28"	sBK/C	Fr/sEXP s/P					
		28-46"	sBK/C1	Fr/sEXP/ss/sP					

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.1945)		
System Type(s)		
Site LTAR		

OTHER FACTORS (.1946):

SITE CLASSIFICATION (.1948)

EVALUATED BY


OTHER(S) PRESENT

FILE # 424118

COMMENTS 10070


LANDSCAPE POSITION	GROUP	TEXTURE	.1955 LTAR	CONSISTENCE MOIST	CONSISTENCE WET
R-RIDGE	I	S-SAND	1.2-0.8		
S-SHOULDER SLOPE		LS-LOAMY SAND		VFR-VERY FRIABLE	NS-NON-STICKY
L-LINEAR SLOPE				FR-FRIABLE	SS-SLIGHTLYSTICKY
FS-FOOT SLOPE	II	SL-SANDY LOAM	0.8-0.6	FI-FIRM	S-STICKY
N-NOSE SLOPE		L-LOAM		VFI-VERY FIRM	VS-VERY STICKY
H-HEAD SLOPE				EFI-EXTREMELY FIRM	NP-NON-PLASTIC
CC-CONCLAVE SLOPE	III	SI-SILT	0.6-0.3		SP-SLIGHTLYSTICKY
CV-CONVEX SLOPE		SICL-SILTY CLAY LOAM			P-PLASTIC
T-TERRACE		CL-CLAY LOAM			VP-VERY PLASTIC
FP-FLOOD PLAIN		SCL-SANDY CLAY LOAM			
	IV	SC-SANDY CLAY	0.4-0.1		
		SIC-SILTY CLAY			
		O-ORGANIC			

STRUCTURE	MINERALOGY
SG-SINGLE GRAIN	SLIGHTLY EXPANSIVE
M-MASSIVE	
CR-CRUMB	EXPANSIVE
GR-GRANULAR	
SBK-SUBANGULAR BLOCKY	
ABK-ANGULAR BLOCKY	
PL-PLATY	
PR-PRISMATIC	



4/29/B

11-07


BK. 07-18
TWP.
CONCORD RD.
TWP.
14.4 AC.(CA)
10
35
34
33
32
31
30
29
28
27
73
7
4
RAMAH CHURCH RD.
#2427
PG 08
70.556 AC
47.511 AC
4.24 AC
FLOOD-PLAIN
RAMAH CREEK
FLOOD-PLAIN
PG. 15
Drive Way
TAX LINE MAP BOOK 11 PAGE 07
MECKLENBURG COUNTY, NORTH CAROLINA
REVISED 5-7-98 MH
SCALE 1" = 400'

FEE: 300.00 ✓

DATE: 4/12/2000

APPLICATION FOR IMPROVEMENT PERMIT
FOR RESIDENTIAL SITE
INDIVIDUAL WATER AND WASTEWATER
SYSTEMS PROGRAM

[ ] CRT

TYPE APPLICATION: ✓ NEW SYSTEM __ EXPANSION/ ALTERATION OF EXISTING SYSTEM __ REPAIR OF EXISTING SYSTEM

NORTH CAROLINA
DEPARTMENT OF ENVIRONMENT,
HEALTH, AND NATURAL RESOURCES
DIVISION OF ENVIRONMENTAL HEALTH
ON-SITE WASTEWATER SECTION

FILE #: 42 9LB

PROPERTY INFORMATION (FROM ENGINEERING FORM) FOR JOB LOCATION: 011-261-31

TAX/PARCEL NUMBER: 011-073- ~~29 80, 31, 35 35~~

STREET ADDRESS: 13015 Ramah Church Road

TYPE OF BUILDING (CHECK ONE):

__ SINGLE MOBILE HOME(S)
__ DOUBLE WIDE (D)
✓ HOUSE (H)
__ MODULAR HOME (M)
__ MULTIPLE FAMILY (U)
__ OTHER (O)

SUBDIVISION OR MOBILE HOME PARK NAME: —

LOT NUMBER: 3, 4, 5, 6, 11

TOWNSHIP (CHECK ONE):

__ 0 MECKLENBURG
__ 1 CHARLOTTE
__ 2 DAVIDSON
__ 3 CORNELIUS
__ 4 PINEVILLE
__ 5 MATTHEWS
✓ 6 HUNTERSVILLE
__ 7 MINT HILL

HEATED SQUARE FOOTAGE:

NUMBER OF BEDROOMS: 6 NUMBER OF OCCUPANTS: 4

CLOSING DATE: 6/15/2000

FOUNDATION FOR RESIDENCE:

✓ WITHOUT BASEMENT
__ ON SLAB
✓ CRAWL SPACE
__ WITH BASEMENT /PLUMBING
__ WITH BASEMENT /NO PLUMBING

IF EXPANSION/ALTERATION OF EXISTING SYSTEM, DESCRIBE THE PROPOSED BUILDING ADDITION:

WILL THERE BE A HOME BUSINESS IN THE RESIDENCE: __ YES ✓ NO TYPE: _____

WATER SUPPLY (CHECK ONE):

__ COMMUNITY (C)
__ MUNICIPAL (M)
✓ PRIVATE WELL (P)
__ SHARED WELL (S)
__ OTHER 'SPRINGS' (O)

IF ANY OF THE FOLLOWING ARE LOCATED ON THE PROPERTY, PLEASE SHOW LOCATION ON PLAT:

BURIED CABLES, LANDFILLS, STUMPHOLES __ YES ✓ NO
EXISTING WASTEWATER SYSTEMS __ YES ✓ NO
EASTMENTS OR RIGHT-OF-WAYS ✓ YES __ NO
WELL, SPRINGS OR WATERLINES ✓ YES __ NO
DESIGNATED WETLANDS __ YES ✓ NO

PROPERTY OWNER:

NAME: Burton (LAST) Jeff (FIRST) (MI)

ADDRESS: 18611 Peninsula Club Dr

CITY: Cornelius STATE: NC ZIP: 28031

DAYTIME PHONE: ( ) —

LEGAL AGENT FOR PROPERTY OWNER, IF APPLICABLE:

NAME: Edwards (LAST) Danny (FIRST) (MI)

DAYTIME PHONE: (704) 996-0117
704 892-6556

WHAT DATE WAS THE PROPERTY ORIGINALLY DEEDED AND RECORDED? 7/98

An Improvement Permit is subject to suspension or revocation if site plans or the intended use change or if information submitted in this application is falsified or changed. The undersigned, owner, or legal agent for the owner, of the property described above as the "Job Location" has read the foregoing application, acknowledges that the contents of same are true, and authorizes agents of the Mecklenburg County Health Department to enter onto the property for the purpose of processing this request.

SIGNED: Danny Edwards DATE: 4/12/2000

MECKLENBURG COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
c/o HAL MARSHALL CTR., SUITE 211, 700 N. TRYON ST., CHARLOTTE, N.C. 28202., (704) 336-5102

BK. 07-18

BK. 07-18

DAVIDSON - HUNTERSVILLE TWP.

CONCORD RD. TWP.

PAGE'S POND CT.

DEWEESE

MAYES

SAM FURR RD.

BLACK FARMS RD.

RAMAH CHURCH RD.

Drive way

RAMAH CREEK

FLOOD-PLAIN

FLOOD-PLAIN

PG. 06

PG. 08

PG. 05

PG. 15

#2427

#2428

011-061-10

14.4 AC.(CA) 10

38.12AC(CA) 11

9.955AC 17

7.85 AC. 22

2.375 AC 1

2.325 AC 21

12 AC. 16

13.72 AC. 20

12 AC. 19

4.279 AC. 26

4.13 AC. 12.

3.95 AC. 13

1.96 AC. 24

15.72 AC (CA) 1

47.511AC 4

3.6 AC(CA) 3

2.39 AC. 2

1.55 AC 23

1.042AC 25

14.52 AC 5

4.24AC 7

70.556AC

73

35 34 33 32 31 30 29 28 27

TAX LINE MAP BOOK 11 PAGE 07
MECKLENBURG COUNTY, NORTH CAROLINA
REVISED 5-7-98 SCALE 1" = 400'

FOR TAX PURPOSES ONLY

MECKLENBURG COUNTY HEALTH DEPARTMENT
Environmental Health Fees

Requestor (please print): JEFF BURTON Phone #: 996.0117 Date Requested: 4.12.00 Date Filled:

Account Name: Cash Charge Account No.:

I certify that I am authorized to charge this account for this service:

Signature: OK #325 (Dawn Edwards) Printed Name: Date:


T.C.	Qty	Description	Unit Cost	Total Cost
0701	1	Improvement Permit Application - Residential	$ 200.00	200.00
0735		Improvement Permit Application - Commercial	$ 400.00	
0702		Optional Site Evaluations	$ 100.00	
0703		Installation and Final Approval	$ 150.00	
0704		Change in Plot Plan	$ 100.00	
0705		MH Exc/Add/Repl without System Modification	$ 100.00	
0706		MH Exc/Add/Repl with System Modification	$ 300.00	
0707		Site Consultation Visit	$ 100.00	
0734		Authorization for Wastewater System Construction	$ 150.00	
0708		Realty Closing - Conventional	$ 85.00	
0709		Realty Closing - FHA with water	$ 135.00	
0710		Additional Trips	$ 65.00	
0711		Well Water Analysis-Bacteriological with regular parameters	$ 50.00	
0712		Well Water Analysis -Nitrates and Nitrites	$ 15.00	
0714		Well Water Analysis - Organic Analysis	$ 200.00	
0715		Admin. Fee - Field Activity Letter	$ 25.00	
0718		Residential Pool Permit	$ 50.00	
0719		Public Pool Permit - operating	$ 240.00	
0720		Seasonal Pool Permit - operating	$ 120.00	
0736		Pool Late Fee	$ 120.00	
0733		Permit to Construct a Public Pool	$ 200.00	
0721		Home Day Care Evaluation and Permit	$ 70.00	
0722		Home Day Care Evaluation and Annual Fee	$ 40.00	
0723		Eval and Report Non-Permit Facility	$ 50.00	
0724		Private Pool Testing	$ 15.00	
0731		Garbage Hauler Permit - (1-9 vehicles)	$ 30.00	
0736		Garbage Hauler Permit - (each over 9)	$ 20.00	
0725		Document Copies	$ 0.05	

Payment received by: Date: Total:

1505 RAMAH CHURCH Road

4/2000

White-AUDIT Canary-CUSTOMER Pink-DIVISION



FOR TAX PURPOSES ONLY

