104630 #10807 X46176

MECKLENBURG COUNTY
HEALTH DEPARTMENT

APPLICATION FOR APPROVAL TO USE AN EXISTING ON-SITE WASTEWATER TREATMENT & DISPOSAL SYSTEM / WATER SUPPLY WELL

APPLICATION TYPE: (●) SEPTIC ONLY ( ) WELL ONLY ( ) SEPTIC & WELL
( ) ADDITION OR RENOVATION WITH OCCUPANCY INCREASE ( ) EXCHANGE MOBILE HOME (SAME # BEDROOMS)
(●) ADDITION OR RENOVATION WITH NO OCCUPANCY INCREASE ( ) COMMERCIAL OR INDUSTRIAL

PERSON FILING APPLICATION:
NAME: Safe Home Pro, Inc.
ADDRESS: PO Box 725
CITY: Huntersville
STATE: NC ZIP: 28070
PHONE: 704-968-3058
ALTERNATE PHONE:
E-MAIL: safehomeprolori@gmail.com

PROPERTY OWNER: ☐ SAME AS PERSON FILING APPLICATION
NAME: Alan Paxton
ADDRESS: 8830 Wedgewood Drive
CITY: Huntersville
STATE: NC ZIP: 28078
PHONE: 704-634-9630
ALTERNATE PHONE:
E-MAIL:

JOB LOCATION INFORMATION
TAX PARCEL #: 01547121
STREET ADDRESS: 8830 Wedgewood Drive
CITY: Huntersville
STATE: NC ZIP: 28078

SUBDIVISION OR MOBILE HOME PARK NAME:
LOT #:

WATER SUPPLY:
( ) MUNICIPAL ( ) PRIVATE WELL (●) PUBLIC WELL ( ) SHARED WELL ( ) OTHER

RESIDENTIAL PROPERTY TYPE: ( ) N/A
(●) HOUSE ( ) MODULAR HOME ( ) MULTIPLE FAMILY
( ) SINGLE MOBILE HOME ( ) DOUBLE WIDE
( ) OTHER

OCCUPANCY (both fields are required):
NUMBER OF BEDROOMS: 3
NUMBER OF OCCUPANTS: 2

COMMERCIAL / INDUSTRIAL PROPERTY TYPE: ☒ N/A
TYPE OF BUSINESS:
EMPLOYEES PER SHIFT:
OF SHIFTS:
INDUSTRIAL WASTES? ( ) YES ( ) NO
UNDERGROUND STORAGE TANKS? ( ) YES ( ) NO

ADDITION/RENOVATION TYPE ATTACHED TO EXISTING STRUCTURE:
☐ BEDROOM ☐ BATHROOM ☐ KITCHEN ☐ DINING ROOM ☐ LIVING ROOM ☐ DEN
☐ GARAGE ☐ SUNROOM ☐ PORCH ☒ DECK ☐ OTHER Installation of a Wooden Deck at

ADDITION/RENOVATION TYPE DETACHED FROM EXISTING STRUCTURE:
☐ DETACHED GARAGE ☐ DETACHED GARAGE WITH PLUMBING ☐ POOL HOUSE ☐ SHOP ☐ BARN
☐ STORAGE SHED ☒ DETACHED PORCH / DECK ☐ OTHER

*The undersigned, owner, or legal agent for the owner, of the property described above as the "Job Location" has read the foregoing application, acknowledges that the contents of same are true, and authorizes the Mecklenburg County Health Department to enter onto the property for the purpose of processing this request.


Lori Owens — Owner's/Agent's Signature
10-17-19 — Date

A PROPOSED PLOT PLAN (see page 2) is required to be submitted with each application.

MECKLENBURG COUNTY – GROUNDWATER & WASTEWATER SERVICES
700 N. TRYON ST. SUITE 211 CHARLOTTE, NC 28202, OFFICE: 704-336-5103, FAX: 704-336-6894

Revised on: 01/03/11

OK TO DES TO INSTALL A Ramp to the front Porch and Bathroom remodel. 10/21/19



NOTE: CONTRACTOR MUST LOCATE UNDERGROUND UTILITIES BEFORE ANY EXCAVATION, BY CALLING 800/632-4949. ALL WORK MUST BE DONE IN ACCORDANCE WITH APPLICABLE STATE AND LOCAL CODES. ALL WORK MUST BE COMPLETE, WITH NO WORK LEFT FOR OTHERS TO DO. WORK INCLUDES ANY ELECTRICAL, PLUMBING, HVAC, OR OTHER WORK NECESSARY TO ACCOMPLISH THE MODIFICATIONS SPECIFIED IN THIS DRAWING.


REV	DESCRIPTION	DATE

NC DIVISION OF
VOCATIONAL REHABILITATION
WESTERN REGION CHARLOTTE, N.C.

TITLE: PAX_ALA RAMP
REFERENCE: NCDVR GENERAL CONDITIONS
MODULAR RAMP CONSTRUCTION DETAILS

EXISTING CONDITIONS

DRAWN BY: T. MILLER
DATE: 3/28/19
SCALE: 1/8"=1'-0"
DRAWING NUMBER: C0000533574
SHEET 1



PROVIDE THE FOLLOWING PER THIS DRAWING, NCDVR GENERAL CONDITIONS, AND APPLICABLE STATE AND LOCAL CODES.

SPECIFICATIONS OF ANY PARTICULAR BRAND INCLUDE OTHERS WHICH ARE SIMILAR OR EQUAL. ALTERNATIVES ARE SUBJECT TO APPROVAL BY ENGINEER PRIOR TO INSTALLATION.

1. PROVIDE 4'-0" X 6'-6" WOOD RAMP OF SLOPE 1:12, FLUSH TO PORCH FLOOR.
2. PROVIDE LEVEL WOOD LANDING 5'-0" X 5'-0", FLUSH TO RAMPS.
3. PROVIDE 4'-0" X 14'-0" WOOD RAMP OF SLOPE 1:12, FLUSH TO LANDING.
4. WIDEN EXISTING CONCRETE SIDEWALK, APPROX. 6-IN WIDE ON BOTH SIDES AS SHOWN TO ACCOMMODATE RAMP. SIDEWALK IS TO EXTEND FROM TOE OF RAMP TO DRIVEWAY, APPROX. 22-FT IN LENGTH.
5. PROVIDE ADJUSTABLE THRESHOLD RAMP FOR DOOR THRESHOLD HEIGHT EQUAL TO 3.5" AND WIDTH EQUAL TO 36". THRESHOLD RAMP MUST NOT INTERFERE WITH OPERATION OF STORM DOOR.
6. INCLUDE NEW RAILINGS FOR ALL PORTIONS OF RAMPS AND LANDINGS.
7. REPAIR ANY LAWN SURFACE AFFECTED BY WORK. INCLUDING GRADING, SEED, AND STRAW AS NEEDED.

NOTE: CONTRACTOR MUST LOCATE UNDERGROUND UTILITIES BEFORE ANY EXCAVATION, BY CALLING 800/632-4949. ALL WORK MUST BE DONE IN ACCORDANCE WITH APPLICABLE STATE AND LOCAL CODES. ALL WORK MUST BE COMPLETE, WITH NO WORK LEFT FOR OTHERS TO DO. WORK INCLUDES ANY ELECTRICAL, PLUMBING, HVAC, OR OTHER WORK NECESSARY TO ACCOMPLISH THE MODIFICATIONS SPECIFIED IN THIS DRAWING.


REV	DESCRIPTION	DATE


NC DIVISION OF
VOCATIONAL REHABILITATION
WESTERN REGION CHARLOTTE, N.C.

TITLE: PAX_ALA RAMP
REFERENCE: NCDVR GENERAL CONDITIONS
MODULAR RAMP CONSTRUCTION DETAILS

MODIFICATIONS

DRAWN BY: T. MILLER
DATE: 3/28/19
SCALE: 1/8"=1'-0"
DRAWING NUMBER: C0000533574
SHEET 2


Huntersville
Huntersville



Solid wood Boards w/ space Between the Boards!

MECKLENBURG COUNTY
Health Department

E. Winters Mabry, MD
Director

(704) 432-3199

Addendum to Application for
New Well or Septic System Installation
Abandonment or Repair of Existing Well or Septic System

Your signature below confirms the following:

1. The information on the application is true, complete and accurate.
2. Authorized county and state officials are granted right of entry to conduct necessary inspections to determine compliances with applicable laws and rules.
3. I acknowledge that Safe Home Pro, Inc is acting as my legal representative (agent) in the submittal of the application for a water supply well or septic permit located at

8830 Wedgewater Dr. Huntersville
Number Street Town
(Or Parcel Number) - 01547121

Alan Paxton
Property Owner (print name)

Property Owner (signature)

10/17/19
Date

MECKLENBURG COUNTY
LAND USE AND ENVIRONMENTAL SERVICES
Payment Receipt

R **Information**

	Date: 10/17/19	**Amount:**	100.00
	Rcpt #: 119040	**Tendered:**	100.00
Check	Auth #: CHARGE	**Returned:**	0.00
Rec	d By: ELLISLW		

Ac **Information**

Acct #: X46176
C tor: SAFE HOME PRO INC
ttn:
ess: P O BOX 725
ess:
City /Zip: HUNTERSVILLE, NC 28070

Item	D cn	Permit#	Quantity	Unit Price	Total Price
0705	U.sc Existing System 8830 Wedgewood DRIVE		1	100.00	100.00

Outstanding Balances

Month-To	Prior Month	30 Days	60 Days	90 Days	Balance