

1833 SWAIM DR

21511128

1/3/2008

duponbj

Groundwater and Wastewater Services File Imaging Project

May 2007

Barcode Font = IDAutomationHC39M

CERTIFICATE OF COMPLETION/OPERATION PERMIT

HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
700 NORTH TRYON ST., SUITE 211
CHARLOTTE, NC 28202
PHONE (704) 336-5102

FILE: 3909 B DATE: 12-15-97

TC: 215-111-08 ☒ L ☐ CRT

SERIAL Nº 17369

Name of Owner GARRY D. SMITH Juris.: _____

Address of Property 1833 SWAIN DRIVE

Inspection Data:

Tank Material PCC

Total Length of Drainfield 300

Number of Lines 5 @ 60

Cover Depth 18" SOIL

Water Supply Source MUNICIPAL

Distance to Water Source 65'

Excavation Inspected 12-15-97

Tank(s) Inspected 12-15-97

Wash Line Inspected NA

High Water Alarm Inspected NA

* INSTALLED ACCORDING TO PERMIT

PLOT

Design 1500 ST INNOVATIVE 900SF I, CEA TYPE III-B CTR# RCS

The undersigned has inspected the Septic Tank System described above, and certifies it has been

☐ installed or constructed ☐ altered or repaired

☑ in accordance with the permit issued ☐ as detailed in the plot above

and meets the provisions of 15A NCAC 18A. 1900, "Laws And Rules For Sewage Treatment and Disposal Systems" in effect on the date of issuance of the permit. This issuance of this

☐ Certificate of Completion ☒ Operation Permit

does not in any way guarantee that the system will operate properly or relieve any person now or hereafter owning, controlling, or using such system from any liability resulting from the failure of the system to operate properly. This document is issued subject to those restrictions and conditions shown on the permit(s) and the provisions of 15A NCAC 18A. 1990 in addition to those listed below under "COMMENTS." This document shall be null and void if any information contained in the application is untrue or if any additions are made to the property which would increase the requirements for said system.

Notice: Disturbance of the designated repair area may result in the suspension/revocation of this permit.

COMMENTS: 3 BRM HOUSE, 1500 SEPAC TANK, 300 FT OF INNOVATIVE/ CHAMBERED DRAIN LINE TYPE III-C SYSTEM

Environmental Health Specialist

Mecklenburg County services are available without regard to ethnic origin, sex, or disability.

INSTALLATION, CONSTRUCTION, ALTERATION, AND/OR REPAIR APPROVAL

HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
700 NORTH TRYON ST., SUITE 211
CHARLOTTE, NC 28202
PHONE (704) 336-5102

FILE: 3909 B DATE: 10-28-97

TC: 215-111-28 ☐L

SERIAL Nº 17523

Permission is hereby given to ✓ Install or Construct, _____ Alter or Repair the individual septic tank wastewater treatment system with subsurface, soil absorption, effluent discharge as specified herein at the described location. This permit is granted based upon the information supplied in the application dated 8-97. All work shall be completed on or before 11-28-97, after which date this permit shall be null and void. The system shall meet all of the construction requirements of 15A NCAC 18A. 1900 which are in effect on the date of the granting of this permit. A Certificate of Completion or an Operation Permit must be obtained from the Mecklenburg County Health Department before any system can be covered up or placed into service. The issuance of this permit does not in any way guarantee that the system anticipated to be constructed will operate properly, or relieve any person now or hereafter owning, controlling or using such system from any liability resulting from the failure of the system to operate properly.

INSTALL ACCORDING TO PLAN ON FILE

PLOT OF SYSTEM

Liquid Capacity of Septic Tank 1500 gallons

Liquid Capacity of Dosing Tank _____ gallons

Tank Construction PCC.

Trench Depth 36"

Absorption and/or Nitrification Lines:

Trench Width 3 feet

Trench Walls Scored and Porous yes

Total Line Length 300 feet

Number of Lines 6

Depth of Stone NA (INNOVATIVE) inches

Distance from House 10' feet

Distance from Property Line 10' feet

Distance from Well ≥50 feet

NOTICE: This system shall not be installed while soils are in a wet condition.

NAME OF OWNER GARRY D. SMITH

LOCATION OF PROPERTY 1833 SWAIN DRIVE

Comments: 1500 ST, INNOVATIVE, 900 SF, T. SAND

J. Andrew Walker
Environmental Health Specialist

WHITE - HEALTH DEPARTMENT's COPY • CANARY - E.H.S. COPY • PINK - OWNER OR AGENT's COPY


PROPOSED PLOT PLAN

HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
700 NORTH TRYON STREET
CHARLOTTE, NC 28202
PHONE (704) 336-5102

FILE: 3909B

TC: 215-111-28

Draw in and name all roads adjoining the property. Draw in and accurately dimension the lot concerned. Accurately indicate property boundaries proposed and/or existing structures and driveways, underground utilities, and wells and springs within 100 feet of the proposed building or drainfield.



X _____
OWNER/AGENT SIGNATURE

DATE 8/15/97

APPROVAL DATE 8/22/97 from B. Mialik, RS

part 1 of 2

White - Health Department's Copy

Canary - E.H.S. Copy

Pink - Owner's Copy

cl ck #6063 D460 DEHT

FEE: 200.00 **AUTHORIZATION FOR WASTEWATER SYSTEM CONSTRUCTION**
DATE: 8/25/97 **VOID SIXTY (60) MONTHS FROM DATE OF ISSUANCE**

DATE: 8/22/97 **PERMIT NO:** 3909B
PARCEL NO: 215-111-28

JOB LOCATION ADDRESS: 1833 Swaim Drive
PROPERTY OWNER: Garry D. Smith
BUILDING CONTRACTOR: Garry D. Smith
SUBDIVISION NAME:
AUTHORIZATION ISSUED BY: Lisa B. Mialik, RS **DATE:** 8/22/97
DEHNR AUTHORIZED AGENT

AUTHORIZATION CONDITIONS

1. WASTEWATER SYSTEM CONSTRUCTION AND INSTALLATION MUST MEET ALL CONDITIONS AND SPECIFICATIONS AS SET FORTH IN IMPROVEMENT PERMIT NO. 3909B, AND THE ATTACHED SITE PLAN WITH SYSTEM DETAILS. CONSTRUCTION AND INSTALLATION MUST ALSO MEET ALL REQUIREMENTS SET FORTH IN THE RULES GOVERNING SANITARY SEWAGE COLLECTION, TREATMENT, AND DISPOSAL AND ANY OTHER APPLICABLE RULES AND LAWS.

2. AN INSTALLATION, CONSTRUCTION, ALTERATION AND/OR REPAIR APPROVAL MUST BE SECURED **PRIOR** TO INSTALLATION OF THE SEPTIC TANK SYSTEM. THE INSTALLER OF THE SYSTEM SHALL BE A REGISTERED SEPTIC TANK CONTRACTOR WITH MECKLENBURG COUNTY HEALTH DEPARTMENT.

3. ANY ALTERATION IN SITE OR SOIL CONDITIONS (INCLUDING LOCATION OF STRUCTURES AND APPURTENANCES) OR MODIFICATION IN USE, DESIGN WASTEWATER FLOW, OR WASTEWATER CHARACTERISTICS AS SPECIFIED IN THE ASSOCIATED IMPROVEMENT PERMIT AND APPLICATION, MAY SUBJECT THIS AUTHORIZATION AND ASSOCIATED PERMIT(S) TO REVOCATION.

4. OTHER CONDITIONS: See conditions of Improvement Permit & associated plot plan.

OWNER CERTIFICATION

I CERTIFY THAT THERE HAVE BEEN NO ALTERATIONS IN SITE OR SOIL CONDITIONS OR MODIFICATIONS TO FACILITY, WASTEWATER FLOW, OR WASTEWATER CHARACTERISTICS FROM THOSE SPECIFIED IN THE ORIGINAL APPLICATION OR ASSOCIATED IMPROVEMENT PERMIT UNLESS AUTHORIZED IN WRITING BY THE MECKLENBURG COUNTY HEALTH DEPARTMENT. I ALSO UNDERSTAND THAT ANY SUCH ALTERATIONS, MODIFICATIONS, OR FALSE INFORMATION ARE GROUNDS FOR REVOCATION OF PERMITS AND AUTHORIZATION TO CONSTRUCT.

X _____ 8/25/97
SIGNATURE OF OWNER/OWNER'S REPRESENTATIVE **DATE**

Permit Number 3909B

CONDITIONS OF IMPROVEMENT PERMIT

1833 Swain Drive

Tax Number 215-111-28

The IMPROVEMENT PERMIT is subject to revocation if site plans or the intended use change. There is to be NO grading, filling or disturbance of the soil in the area of the septic tank system or repair area.

CONSTRUCTION AUTHORIZATION must be obtained prior to receiving a Building Permit. The Construction Authorization is NOT transferable. Do not clear, grade, fill or disturb soil prior to obtaining a Construction Authorization.

Domestic-type wastewater only. No industrial process wastewater may be discharged into the system.

Basement: ___ Yes ✓ No ___ Partial Basement

Type Primary Wastewater System Type (circle one): I II (III) IV V VI

___ Conventional
___ Prefabricated, permeable block panel system
___ Shallow Placed Conventional
___ Low Pressure Pipe
___ Large Diameter Pipe
___ Fill
___ Other
✓ Innovative or Experimental: 25% reduction design
___ IWWS-93-1
___ IWWS-93-2
___ IWWS-94-1

3 Long-term acceptance rate	360 Max gallons/day wastewater flow	900 Absorption Area (sq ft)	9' Trench spacing (min. on centers)
NO municipal Serviced by private well	1500 Gallon septic tank	300 Total trench length (ft)	36" Maximum trench depth (At least 12" of provisionally suitable soil must remain between trench bottom and unsuitable soil conditions)
3 Bedrooms in residence	NO Gallon pump tank	Backfill to Depth of stone manufacturers specifications	

Any surface waters present: NO Type: Minimum separation distance:

Site modifications required:

Additional Conditions: keep waterline 10' minimum from any portion of the sewage disposal system & its designated repair area.
- Plumb house high in order to accommodate shallow placement of septic tank.
- Keep installation 50' minimum from ANY WELL + 15' from drainfield @ 1833 Swain Drive

Exempt from 100% repair per .1945(c)(1)

Repair Area System Type Type (circle one): I II (III) IV V VI

___ Conventional
___ Prefabricated, permeable block panel system
___ Shallow Placed Conventional
___ Low Pressure Pipe
___ Large Diameter Pipe
___ Fill
___ Other
___ Innovative or Experimental:
___ IWWS-93-1
___ IWWS-93-2
___ IWWS-94-1

___ Absorption Area (Sq ft) ___ Total Trench Length (Ft)	___ Depth of Stone Trench	9' Trench spacing (min. on centers)	36" Maximum Trench Depth

For existing system, enter the year originally installed: NA

The undersigned, an authorized agent of the MECKLENBURG COUNTY HEALTH DEPARTMENT, certifies that the Department has approved the Request for the Job Location contained in this document. This approval is granted in accordance with the provisions of Laws and Rules For Sewage, Treatment and Disposal in effect at the time of issuance of the permit and is subject to the following provisions:

... No work shall be conducted on the septic tank system until an Installation, Construction, Alteration and/or Repair Approval is granted by this Department.

... This Improvement permit is transferable.

Improvement Permit valid 5 years from date of issuance.

Innovative design at owner's request in attempt to save large tree near back of property.

Lisa B. Malik, RS 8/22/97
DEHNR Authorized Agent Date

X _____ 8/25/97
Owner/Agent Signature Date

MECKLENBURG COUNTY
HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
c/o HAL MARSHALL CTR.
SUITE 211
700 N. TRYON ST.
CHARLOTTE, N.C. 28202.
(704) 336-5102

NORTH CAROLINA DEPARTMENT OF
ENVIRONMENTAL, HEALTH,
AND NATURAL RESOURCES
DIVISION OF ENVIRONMENTAL HEALTH
ON-SITE WASTEWATER SECTION

part 2 of 2

DIVISION OF ENVIRONMENTAL HEALTH
ON-SITE WASTEWATER SECTION

0400

COUNTY: _____

SOIL/SITE EVALUATION for ON-SITE WASTEWATER SYSTEM

#1 3909B 215-111-28

OWNER: Gary D. Smith APPLICANT: _____ DATE EVALUATED: _____
ADDRESS: PO Box 576, Mathews APPLICATION DATE: _____ PROPERTY SIZE: .46
PROPOSED FACILITY: residence PROPOSED DESIGN FLOW (.1949): 360gpd PROPERTY RECORDED: _____
LOCATION OF SITE: 1833 Swann Dr.
WATER SUPPLY: ☐ Private ☑ Public ☐ Well ☐ Spring ☐ Other _____
EVALUATION METHOD: ☑ Auger Boring ☐ Pit ☐ Cut
TYPE OF WASTEWATER: ☑ Sewage ☐ Industrial Process ☐ Mixed

PROFILE #	Slopes 3-6% .1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941) .1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE/ MINERALOGY	OTHER PROFILE FACTORS .1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	1956 SAPRO CLASS	.1944 RESTR HORIZ	PROFILE CLASS & LTAR
1	LS	0-12"	gr l sc l	Fr/SExP/ss/sP	>48" To soil wetness	48"	N/A	None	PS .39/F2 IV
		12-48"	sBK/c	Fi/SExP/s/P					
2	LS	0-10"	gr l sc l	Fr/SExP/ss/sP	>46" To soil wetness	46"	N/A	None	PS .39/F2 IV
		10-48"	sBK/c	Fi/SExP/s/P					
3	LS	0-8"	gr l sc l	Fr/SExP/ss/sP	>51" To soil wetness	51"	N/A	None	PS .39/F2 IV
		8-51"	sBK/c	Fi/SExP/s/P					
4	LS	0-6"	gr l sc l	Fr/SExP/ss/sP	>48" To soil wetness	48"	N/A	None	PS .39/F2 IV
		6-48"	sBK/c	Fi/SExP/s/P					

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.1945)	PS	
System Type(s)		
Site LTAR		

OTHER FACTORS (.1946): _____
SITE CLASSIFICATION (.1948): Provisionally Suitable
EVALUATED BY: W.A. Marlin 8-16-97
OTHER(S) PRESENT: LES

COMMENTS: Does not appear to be 100% Repair

LEGEND

use the following standard abbreviations

LANDSCAPE POSITION	GROUT	SOIL TEXTURE	CONVENTIONAL 1955 LTAR	LPP 1957 LTAR	MINERALOGY/ CONSISTENCE	STRUCTURE
C (Concave Slope) V (Convex Slope) (Drainage Way) S (Debris Slump) P (Flood Plain) S (Foot Slope) (Head Slope) (Linear Slope) (Nose Slope) (Ridge) (Shoulder Slope) (Terrace)	I	S (Sand) LS (Loamy Sand)	1.2 - 0.8	0.6 - 0.4	NEXP (Non-expansive) SEXP (Slightly Expansive) EXP (Expansive)	G (Single Grain) M (Massive) CR (Crumb) GR (Granular) SBK (Subangular Blocky) ABK (Angular Blocky) PL (Platy) PR (Prismatic)
	II	SL (Sandy Loam) L (Loam)	0.8 - 0.6	0.4 - 0.3		
	III	SI (Silt) SICL (Silty Clay Loam) CL (Clay Loam) SCL (Sandy Clay Loam) SUC (Silt Loam Clay)	0.6 - 0.3	0.3 - 0.15		
					MOIST	WET
	IV	SC (Sandy Clay) SIC (Silty Clay)	0.4 - 0.1	0.2 - 0.05	VFR (Very Friable) FR (Friable) FI (Firm) VFI (Very Firm v. Very Sticky) EFI (Extremely Firm)	NS (Non-sticky) SS (Slightly Sticky) S (Sticky) VS (Very Sticky) NP (Non-plastic) SP (Slightly Plastic) P (Plastic) VP (Very Plastic)
		O (Organic)	None			

NOTES


HORIZON DEPTH In inches below natural soil surface
DEPTH OF FILL In inches from land surface
RESTRICTIVE HORIZON Thickness and depth from land surface
SAPROLITE S(suitable) or U(unsuitable)
SOIL WETNESS Inches from land surface to free water or inches from land surface to soil colors with chroma 2 or less - record Munsell color chip designation
CLASSIFICATION S (Suitable), PS (Provisionally Suitable), or U (Unsuitable)

Evaluation of saprolite shall be by pits.
Long-term Acceptance Rate (LTAR): gal/day/ft²

Show profile locations and other site features (dimensions, reference or benchmark, and North).

3909B

112



LDS

LDS
Land Development Services
1815 Park Drive
Charlotte, NC 28204
Tele: 704/333-5390
Fax: 704/376-0629

FAX Communication To:
LISA MALIK

From:
BOB DAVIS

Number of pages transmitted, including this cover sheet 2


Transmission Date 8/20/97

Comments
Revised Section 2.0

16th Day of July 1997

Signed Robert E. Rembert

LDS
Land Development Services
1815 Park Drive
Charlotte, NC 28204
Tele: 704/333-5390



VICINITY MAP
Not To Scale

Deed 3681-581
Now or formerly

S. 51-22 E. 100.0

N.I.P.

Deed 3652-903
Now or Formerly

NORTH CAROLINA
REGISTERED
SEAL
L1055
LAND SURVEYOR
ROBERT E. REMBERT

Deed 2187-595
Now or Formerly

E.I.P.

185.21

N. 36-38 E.

46.16'

27'

HOUSE
STAKED

184.72

N. 38-39-10 E.

Deed 2900-329
Now or Formerly

E.I.P.

100.10'

S. 51-39-19 E.

E.I.P.

430' E. Hwy. 51

SWAIN DR

Lot Line Data Copied From Actual Record Map

0 30'

SURVEY of
Property at 45 Swain
Charlotte, NC.
Property of

This Drawing Not Completed To NCGS47-30 Requirements And Is NOT Suitable For Recordation.


Scale 1" = 30' Deed Recorded 4211-595 Map Recorded

File 39098

16th Day of July 1997

Signed Robert E. Rembert

LDS
Land Development Service
1815 Park Drive
Charlotte, NC 28204
Tele: 704/333-5380



VICINITY MAP
Not To Scale

Deed 3897-581
Now or Formerly

S. 51-22 E. 100.0

N.I.P.

Deed 3652-903
Now or Formerly

NORTH CAROLINA REGISTERED SEAL X L1055 LAND SURVEYOR ROBERT E. REMBERT

E.I.P.

Deed 2687-333
Now or Formerly

185.21

N. 38-38 E.

Deed 2687-333

184.72

N. 38-36-10 E.

Deed 2906-79
Now or Formerly

46'-6"

27'

House Staked

45'

50'

E.I.P.

100.10

E.I.P.

S. 51-38-49 E.

29.8

430' ± Hwy. 51

SWAIM DR

Boundary SURVEY of
Property As Shown
Charlotte, N.C.

Property of

Lot Line Data Copied From Noted Record Map.

0 30'

This Drawing Not Prepared to NC 6547-30 Requirements And Is NOT Suitable For Recordation

Scale 1" = 30' Deed Recorded 4219-595 Map Recorded

Rec 39098

TO: Lisa Malik

FROM: Mike Jones

Century 21 Homes 948752-

File 3909B

DEED BOOK PAGE
4219 0595

PRESENTED FOR REGISTRATION
Aug 19 11 2 54 '79
REGISTER OF DEEDS MECKLENBURG CO N.C.
56

STATE OF N.C. Real Estate Excise Tax $4.00

Excise Tax | Recording Time, Book and Page

Tax Lot No. Parcel Identifier No.
Verified by County on the day of , 19
by

Mail after recording to R H Keesler + wife Marilyn H. Keesler
1825 Swaim Drive Matthews, NC 28105
This instrument was prepared by Nick J. Miller, 701 E. Trade St., Charlotte, N. C. 28202

NORTH CAROLINA GENERAL WARRANTY DEED

THIS DEED made this 8 day of August , 19 79 , by and between

GRANTOR	GRANTEE
PAUL R. HAGER and wife, FANNIE L. HAGER	RICHARD H. KEESLER and wife, MARILYN H. KEESLER 1825 Swaim Drive Matthews, North Carolina 28105

Enter in appropriate block for each party: name, address, and, if appropriate, character of entity, e.g. corporation or partnership.

The designations Grantor and Grantee as used herein shall include said parties, their heirs, successors, and assigns, and shall include singular, plural, masculine, feminine or neuter as required by context.

WITNESSETH, that the Grantor, for a valuable consideration paid by the Grantee, the receipt of which is hereby acknowledged, has and by these presents does grant, bargain, sell and convey unto the Grantee in fee simple, all that certain lot or parcel of land situated in Morning Star Township, Mecklenburg County, North Carolina and more particularly described as follows:

BEGINNING at a point in the center line of Swaim Drive, which point is located South 51-22 East 630.00 feet from the center line of the Matthews-Mint Hill Road (N. C. Highway #51), said point also being the southernmost corner of the property conveyed by Hannah Harkey to Harold B. Traywick and wife, Bobbie Rose Traywick by Deed recorded in Book 2667, Page 419, Mecklenburg County Registry, and runs thence with the line of the Traywick (now or formerly) property North 38-38 East 215.00 feet to an iron, the easternmost corner of said Traywick (now or formerly) property, thence South 51-22 East 100 feet to an old iron, the northerly corner of the property conveyed by Hannah Harkey to Paul R. Hager and wife, Fannie L. Hager by Deed recorded in Book 2662, Page 305, said Registry, thence running with the line of the Hager property South 38-38 West 215.00 feet to a point in the center line of Swaim Drive, thence with said center line of Swaim Drive North 51-22 West 100.00 feet to the point or place of Beginning.

N.C. Bar Assoc. Form No. 3 © 1976

File 3909B

DEED BOOK 4219 PAGE 0595

STATE OF NORTH CAROLINA Real Estate Excise Tax $4.00

PRESENTED FOR REGISTRATION
Aug 10 11 20 AM '79
REGISTER OF DEEDS MECKLENBURG CO N.C.
56

Excise Tax

Recording Time, Book and Page

Tax Lot No. ..... Parcel Identifier No. .....

Verified by ..... County on the ..... day of ....., 19.....

by .....

Mail after recording to R H Keesler + wife Marilyn H. Keesler
1825 Swaim Drive Matthews, NC 28105

This instrument was prepared by Nick J. Miller, 701 E. Trade St., Charlotte, N. C. 28202

NORTH CAROLINA GENERAL WARRANTY DEED

THIS DEED made this 8 day of August, 19 79, by and between

GRANTOR	GRANTEE
PAUL R. HAGER and wife, FANNIE L. HAGER	RICHARD H. KEESLER and wife, MARILYN H. KEESLER 1825 Swaim Drive Matthews, North Carolina 28105

Enter in appropriate block for each party: name, address, and, if appropriate, character of entity, e.g. corporation or partnership.

The designation Grantor and Grantee as used herein shall include said parties, their heirs, successors, and assigns, and shall include singular, plural, masculine, feminine or neuter as required by context.

WITNESSETH, that the Grantor, for a valuable consideration paid by the Grantee, the receipt of which is hereby acknowledged, has and by these presents does grant, bargain, sell and convey unto the Grantee in fee simple, all that certain lot or parcel of land situated in Morning Star Township, Mecklenburg County, North Carolina and more particularly described as follows:

BEGINNING at a point in the center line of Swaim Drive, which point is located South 51-22 East 430.00 feet from the center line of the Matthews-Mint Hill Road (N. C. Highway 51), said point also being the southernmost corner of the property conveyed by Hannah Harkey to Harold B. Traywick and wife, Bobbie Rose Traywick by Deed recorded in Book 2663, Page 419, Mecklenburg County Registry, and runs thence with the line of the Traywick (now or formerly) property North 38-38 East 215.00 feet to an iron, the easternmost corner of said Traywick (now or formerly) property, thence South 51-22 East 100 feet to an old iron, the northerly corner of the property conveyed by Hannah Harkey to Paul R. Hager and wife, Fannie L. Hager by Deed recorded in Book 2462, Page 305, said Registry, thence running with the line of the Hager property South 38-38 West 215.00 feet to a point in the center line of Swaim Drive, thence with said center line of Swaim Drive North 51-22 West 100.00 feet to the point or place of Beginning.

1000 CRK # 5844
7/8/97 gc

APPLICATION FOR IMPROVEMENT PERMIT FOR RESIDENTIAL SITE INDIVIDUAL WATER AND WASTEWATER SYSTEMS PROGRAM

[ ] CRT

TYPE APPLICATION: ___ NEW SYSTEM __ EXPANSION/ ALTERATION OF EXISTING SYSTEM ___ REPAIR OF EXISTING SYSTEM

NORTH CAROLINA
DEPARTMENT OF ENVIRONMENT,
HEALTH, AND NATURAL RESOURCES
DIVISION OF ENVIRONMENTAL HEALTH
ON-SITE WASTEWATER SECTION

FILE #: 39098

PROPERTY INFORMATION (FROM ENGINEERING FORM) FOR JOB LOCATION:

TAX/PARCEL NUMBER: # 215-111-28

STREET ADDRESS: 1833 Swaim Dr

SUBDIVISION OR MOBILE HOME PARK NAME:

LOT NUMBER: #

TYPE OF BUILDING (CHECK ONE):

___ SINGLE MOBILE HOME(S)
___ DOUBLE WIDE (D)
✓ HOUSE (H)
___ MODULAR HOME (M)
___ MULTIPLE FAMILY (U)
___ OTHER (O)

TOWNSHIP (CHECK ONE):

___ 0 MECKLENBURG
___ 1 CHARLOTTE
___ 2 DAVIDSON
___ 3 CORNELIUS
___ 4 PINEVILLE
✓ 5 MATTHEWS
___ 6 HUNTERSVILLE
___ 7 MINT HILL

HEATED SQUARE FOOTAGE: 1137

NUMBER OF BEDROOMS: 3 | NUMBER OF OCCUPANTS: 2

CLOSING DATE 10/31/97

FOUNDATION FOR RESIDENCE:

___ WITHOUT BASEMENT
✓ ON SLAB
___ CRAWL SPACE
___ WITH BASEMENT /PLUMBING
___ WITH BASEMENT /NO PLUMBING

IF EXPANSION/ALTERATION OF EXISTING SYSTEM, DESCRIBE THE PROPOSED BUILDING ADDITION:

N/A

WILL THERE BE A HOME BUSINESS IN THE RESIDENCE: ___ YES ✓ NO TYPE: _____

WATER SUPPLY (CHECK ONE):

___ COMMUNITY (C)
✓ MUNICIPAL (M)
___ PRIVATE WELL (P)
___ SHARED WELL (S)
___ OTHER 'SPRINGS' (O)

IF ANY OF THE FOLLOWING ARE LOCATED ON THE PROPERTY, PLEASE SHOW LOCATION ON PLAT:

BURIED CABLES, LANDFILLS, STUMPHOLES ___ YES ✓ NO
EXISTING WASTEWATER SYSTEMS ___ YES ✓ NO
EASTMENTS OR RIGHT-OF-WAYS ___ YES ✓ NO
WELL, SPRINGS OR WATERLINES ___ YES ✓ NO
DESIGNATED WETLANDS ___ YES ✓ NO

PROPERTY OWNER:	LEGAL AGENT FOR PROPERTY OWNER, IF APPLICABLE:
NAME: (LAST) Smith (FIRST) Gerry (MI) D.	NAME: (LAST) (FIRST) (MI)
ADDRESS: P.O. Box 578	DAYTIME PHONE: ( ) —
CITY: Matthews STATE: NC ZIP: 28106	
DAYTIME PHONE: 704 282-4909	

WHAT DATE WAS THE PROPERTY ORIGINALLY DEEDED AND RECORDED? _____

An Improvement Permit is subject to suspension or revocation if site plans or the intended use change or if information submitted in this application is falsified or changed. The undersigned, owner, or legal agent for the owner, of the property described above as the "Job Location" has read the foregoing application, acknowledges that the contents of same are true, and authorizes agents of the Mecklenburg County Health Department to enter onto the property for the purpose of processing this request.

SIGNED: _____ DATE 6/13/97

MECKLENBURG COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
c/o HAL MARSHALL CTR., SUITE 211, 700 N. TRYON ST., CHARLOTTE, N.C. 28202., (704) 336-5102


PROPOSED PLOT PLAN

HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
700 NORTH TRYON STREET
CHARLOTTE, NC 28202
PHONE (704) 336-5102

FILE: 39893

TC: 215-111-28

Draw in and name all roads adjoining the property. Draw in and accurately dimension the lot concerned. Accurately indicate property boundaries proposed and/or existing structures and driveways, underground utilities, and wells and springs within 100 feet of the proposed building or drainfield.



OWNER/AGENT SIGNATURE

DATE 6/13/97

APPROVAL DATE _____

White - Health Department's Copy

Canary - E.H.S. Copy

Pink - Owner's Copy

File
3908B

Mecklenberg Health Department
July 4, 1997

Please accept this note as permission for Gary Smith to have a perk test done on our lot on Swaim Drive. The address is 1833 Swaim Drive.

Thank you,

Richard Hunter