

3321 MINTWOOD DR

19521143

1/9/2008

duponbj

Groundwater and Wastewater Services File Imaging Project
May 2007
Barcode Font = IDAutomationHC39M

marked as County copy 4/5/06

STANLEY SEPTIC SERVICE, INC.

STATE OF NORTH CAROLINA
COUNTY OF Mecklenburg County

INSPECTION AND MAINTENANCE AGREEMENT (rev.11/01)

704-892-1129

THIS AGREEMENT is made and entered into this 22nd day of March, 2006, by and between Lisa MacLellan ("Owner") and Stanley Septic Service, Inc (hereinafter the "Contractor").

WITNESSETH

WHEREAS, the Owner owns or controls the property upon which a ground absorption sewage treatment system (hereinafter "system") is installed, such system designated a Type IV system under the Rules for Sanitary Sewage Collection, Treatment and Disposal found at 15A N.C. Admin. Code 18A.1900 *et seq.*; and

WHEREAS, 15A N.C. Admin. Code 18A.1961 requires a contract to be executed between the system owner and a management entity prior to the issuance of an Operation Permit for said system; and

WHEREAS, 15A N.C. Admin. Code 18A.1961 requires that a condition of the Operation Permit for said system be that a properly executed contract between the system owner and a management entity shall be in effect as long as the system is in use; and

WHEREAS, the Contractor is a management entity of a type authorized by the 15A N.C. Admin. Code 18A.1961 to manage a Type IV system.

NOW THEREFORE, in consideration of the premises and of the mutual covenants and promises contained in this Agreement, it is hereby agreed by and between the Owner and the Contractor as stipulated below.

1. **The Contractor's Obligations.** The Contractor shall perform the following services on the Owners system located at: 3321 Mintwood Dr., Charlotte, NC 28227.

   a. The Contractor shall inspect the system at least at the frequency required in Table V (b) of 15A N.C. Admin. Code 18A.1961(b) for a Type IV System.

   b. The Contractor perform the following routine maintenance procedures in accordance with the conditions of the Operation Permit:

      (1) [from operation permit]
      (2)
      (3)

   c. The Contractor shall report the results of its inspections to the local health department at the frequency IV System.

d. If an inspection indicates the need for system repairs, the Contractor shall notify the local health department within 48 hours of the inspection.

e. The Contractor shall notify the Owner of needed repairs, which are outside the scope of routine maintenance described in subparagraph (b) above. The Contractor shall perform necessary repairs to the system at the request of the Owner and shall be entitled to payment therefore at the Contractors normal charge for services and materials.

f. The Contractor shall employ or shall contract with a certified operator(s) if required by Table V (b) of 15A N.C. Admin. Code 18A.1961(b) for a Type IV System.

g. The Contractor shall respond to a request for a nonscheduled service or maintenance call within 24 hours after receipt of such request.

2. The Owners Obligations.

a. The Owner shall pay to the Contractor the sum agreed upon, per year for periodic inspections, routine maintenance procedures and periodic reports. The annual fee may be amended upon sixty (60) days advance notice to the Owner. The Owner shall pay to the Contractor his normal and customary fees for any work performed on the system as a result of nonscheduled service or maintenance calls. All fees are due and payable within ten (10) days of billing. Payment due to the Contractor and unpaid by the Owner after ten (10) days shall accrue interest from the due date until paid.

b. Within seven (7) days of receipt of notice of needed repairs pursuant to paragraph 1c. above, the Owner shall request the Contractor to complete needed repairs or shall provide to the Contractor evidence that the needed repairs were satisfactorily completed by another entity.

c. The Owner shall provide the Contractor with such access to the system as is reasonably necessary for the Contractor to comply with the terms of this Agreement.

3. Term. This Agreement shall remain in effect until terminated

a. Automatic Termination.
This agreement shall automatically terminate if the Operation Permit for the system is revoked and all appeals of the revocation are exhausted or time for taking appeal has passed.

b. Termination by Mutual Consent.
The Parties may mutually agree to terminate this Agreement by giving written notice of termination by mutual consent to the local health department thirty (30) days in advance of the date of termination.

c. Termination by the Owner.
The Owner may terminate this Agreement by giving notice to the Contractor and to the local health department **thirty (30) days** in advance of the termination.

d. Termination by the Contractor

(1) The Contractor may terminate this Agreement for the cause by giving written notice of intent to terminate this Agreement to the Owner and to the local health department **thirty (30) days** in advance of the date of termination. Cause shall be defined as:

(a) Failure to remit payment for any bill for services performed under and in accordance with this Agreement if said is not paid within ten **(10) days** of receipt by the Owner of the bill. If said bill is paid after notice of termination is given but prior to the date of termination of this Agreement, this Agreement shall continue in effect; or

(b) Failure of the Owner to provide to the Contractor authorization to complete needed repairs or satisfactory evidence that the needed repairs to the system were completed by another entity within seven (7) days of receipt of notice of needed repairs pursuant to paragraph i.e. above. If said authorization to complete needed repairs or evidence of completion of said repairs is provided after notice of termination of this Agreement, this Agreement shall continue in effect;

(c) Failure of the Owner to allow the Contractor such access to the system as is reasonably necessary in order for the Contractor to comply with the terms of this Agreement.

(2) The Contractor may not terminate this Agreement without cause, but may assign its rights and duties under this Agreement as provided in paragraph 4, below

4. <u>Assignment</u>.

a. Assignment by the Owner. The Owner shall notify the Contractor of the name and address of any purchaser of the property on which the system is located. The Owner shall also notify any purchaser of the property on which the system is located of the existence of this Agreement and shall assign all rights and duties under this Agreement to said purchaser.

b. Assignment by the Contractor. The Contractor may assign its rights and duties under this Agreement to another management entity, which is qualified pursuant to 15A N.C. Admin. Code 18A.1961 to manage a Type IV system upon thirty (30) days written notice to the Owner and to the local health department.

5. **Use of Subcontractors.** The Contractor may subcontract with such manufacturers, suppliers and contractors, as it deems desirable to perform any of the Contractors duties under this Agreement. The Contractor shall at all times remain responsible for the performance of and payment for all work performed by all subcontractors.

6. **Representations.** The Parties represent to each other that each has the power, authority and legal right to enter into and perform its obligations as set forth in this Agreement.

7. **Regulatory Amendments.** Reference in this Agreement to sections of the Administrative Code shall include such rules as they may be amended in the future

8. **No Implied Waver.** The waiver by either Party of a default or a breach by the other Party of any provision of this Agreement shall not operate or be construed to operate as a waiver of any subsequent default or breach. The failure at any time of either Party to enforce any provision of this Agreement (a) shall not be construed to be a waiver of such provisions, or of any other provision; and (b) shall not in any way affect the validity of this Agreement, or any part of this Agreement, or the right of either Party thereafter to enforce each and every provision of this Agreement.

9. **Notice.** Every notice required under this Agreement shall be in writing and shall be deemed sufficiently given if delivered in person or sent by certified or registered mail, return receipt requested, postage prepaid to the Party to be notified and addressed as follows:

To the Owner: Lisa MacLellan
3321 Mintwood Dr.
Charlotte, NC

To the Contractor: Stanley Septic Service, Inc
PO Box 184
Stanley, NC 28164

To the Local Health Department: Mecklenburg County

The date of any Notice shall be the date of personal delivery or the date shown on the return receipt as the date of delivery or attempted delivery, as the case may be. Changes in the respective addresses to which notice may be directed may be made from time to time by either Party by notice to the other party.

10. **Place of Agreement.** This Agreement and any questions concerning its validity, construction or performance shall be governed by the laws of the State of North Carolina, notwithstanding the place of execution, or the order in which the signatures of the Parties are affixed.

11. **Entire Agreement and Amendment.** This Agreement supersedes all prior negotiations, agreements and understandings between the Parties with respect to the subject matter hereof and constitutes the entire Agreement between the Parties with respect to the subject matter hereof. To be effective, any amendment or modification to this Agreement must be in writing and must be signed by the Parties.

12. **Severability.** In the event that any provision of this Agreement shall, for any reason, be determined to be invalid, illegal of unenforceable in any respect, the Parties shall negotiate in good faith and agree to such amendments, modifications or supplements of or to this Agreement or such other appropriate actions as shall, to the maximum extent practicable in light of such determination, implement and give effect to the intentions of the Parties as reflected in this Agreement, and the other provisions of this Agreement shall, as so amended, modified, supplemented or otherwise affected by such action, remain in full force and effect.

IN TESTIMONY WHEREOF, The Parties hereto have executed this Agreement in duplicate originals, one of which is retained by each of the Parties, the day and year first above written.

Attest: _____ Lisa MacLellan
(Owner)

Stanley Septic Service, Inc
(Contractor)

Attest:

(hr:mecontract.gm)

CERTIFICATE OF COMPLETION/OPERATION PERMIT

HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
700 NORTH TRYON ST., SUITE 211
CHARLOTTE, NC 28202
PHONE (704) 336-5102

FILE: 5786B DATE: 3/20/06

TC: 195211 43 ☐ L ☐ CRT

SERIAL 19953

Name of Owner Lisa L. MacLellan Juris.: _____

Address of Property 3321 Mintwood Dr

Inspection Data:

Tank Material PCC

Total Length of Drainfield 324'

Number of Lines 6 @ 54

Cover Depth 6" - 8"

Water Supply Source Municipal

Distance to Water Source >10'

Excavation Inspected 3/17/06 PSW

Tank(s) Inspected 3/20/06

Wash Line Inspected NA

High Water Alarm Inspected 3/20/06 DC

septic system installed in accordance w/ approved plot plan. Repair area alteration noted on plot plan. PSW

PLOT

Design 2006, 1500ST, 1000DT, PI, MDD, 254'PPBPS CTR# Stanley Septic

The undersigned has inspected the Septic Tank System described above, and certifies it has been

☒ installed or constructed ☐ altered or repaired

☒ in accordance with the permit issued ■ as detailed in the plot above

and meets the provisions of I5A NCAC 18A. 1900, "Laws And Rules For Sewage Treatment and Disposal Systems" in effect on the date of issuance of the permit. This issuance of this

☐ Certificate of Completion ☒ Operation Permit

does not in any way guarantee that the system will operate properly or relieve any person now or hereafter owning, controlling, or using such system from any liability resulting from the failure of the system to operate properly. This document is issued subject to those restrictions and conditions shown on the permit(s) and the provisions of I5A NCAC 18A. 1990 in addition to those listed below under "COMMENTS." This document shall be null and void if any information contained in the application is untrue or if any additions are made to the property which would increase the requirements for said system.

Notice: Disturbance of the designated repair area may result in the suspension/revocation of this permit.

COMMENTS: Septic System Designed for a 4 bedroom residence Type IVa PPBPS

Environmental Health Specialist

Mecklenburg County services are available without regard to ethnic origin, sex, or disability.

INSTALLATION, CONSTRUCTION, ALTERATION, AND/OR REPAIR APPROVAL

HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
700 NORTH TRYON ST., SUITE 211
CHARLOTTE, NC 28202
PHONE (704) 336-5102

FILE: 5786 B DATE: 3/17/06

TC: 195 211 43 ☐ L

SERIAL 19905

Permission is hereby given to ✓ Install or Construct, _____ Alter or Repair the individual septic tank wastewater treatment system with subsurface, soil absorption, effluent discharge as specified herein at the described location. This permit is granted based upon the information supplied in the application dated 1/5/05. All work shall be completed on or before 4/17/06, after which date this permit shall be null and void. The system shall meet all of the construction requirements of I5A NCAC 18A. 1900 which are in effect on the date of the granting of this permit. A Certificate of Completion or an Operation Permit must be obtained from the Mecklenburg County Health Department before any system can be covered up or placed into service. The issuance of this permit does not in any way guarantee that the system anticipated to be constructed will operate properly, or relieve any person now or hereafter owning, controlling or using such system from any liability resulting from the failure of the system to operate properly.

See approved plot plan

PLOT OF SYSTEM

Liquid Capacity of Septic Tank 1500 gallons

Liquid Capacity of Dosing Tank 1000 gallons

Tank Construction PCC

Trench Depth 28"

Absorption and/or Nitrification Lines:

Trench Width 3' feet

Trench Walls Scored and Porous Yes

Total Line Length 324 feet

Number of Lines 6 (54')

Depth of Stone NA inches

Distance from House 5' feet

Distance from Property Line 10' feet

Distance from Well >100' feet
710' Municipal

NOTICE: This system shall not be installed while soils are in a wet condition.

NAME OF OWNER Lisa McClellan Lot 1

LOCATION OF PROPERTY 3321 Mintwood Dr

Comments: Septic system to be installed in accordance w/ approved plot plan, Repair area to be altered on plan

Phila D. Walker RS
Environmental Health Specialist

WHITE - HEALTH DEPARTMENT's COPY • CANARY - E.H.S. COPY • PINK - OWNER OR AGENT's COPY

FEE: 300.00

DATE: 4/3/2006

CONSTRUCTION AUTHORIZATION FOR AN ON-SITE WASTEWATER TREATMENT & DISPOSAL SYSTEM

MECKLENBURG COUNTY

GROUNDWATER & WASTEWATER SERVICES

FILE NUMBER: 5786B

PERMIT NUMBER: 30000608

PARCEL NUMBER: 19521143

JOB LOCATION INFORMATION

ADDRESS: 3321 MINTWOOD DR

CITY: CHARLOTTE **STATE: NC** **ZIP:** 28227

ISSUED TO: LISA L. MACLELLAN

CONSTRUCTION AUTHORIZATION ISSUANCE DATE: 11/7/2005

CONSTRUCTION AUTHORIZATION CONDITIONS

1. WASTEWATER SYSTEM CONSTRUCTION AND INSTALLATION MUST MEET ALL CONDITIONS AND SPECIFICATIONS AS SET FORTH IN IMPROVEMENT PERMIT NUMBER 30000608, AND THE ATTACHED SITE PLAN WITH SYSTEM DETAILS. CONSTRUCTION AND INSTALLATION MUST ALSO MEET ALL REQUIREMENTS SET FORTH IN THE RULES GOVERNING SANITARY SEWAGE COLLECTION, TREATMENT, AND DISPOSAL AND ANY OTHER APPLICABLE RULES AND LAWS.

2. AN INSTALLATION APPROVAL MUST BE SECURED PRIOR TO INSTALLATION OF THE SEPTIC TANK SYSTEM. THE INSTALLER OF THE SYSTEM SHALL BE A REGISTERED SEPTIC TANK CONTRACTOR WITH THE MECKLENBURG COUNTY HEALTH DEPARTMENT.

3. ANY ALTERATION IN SITE OR SOIL CONDITIONS (INCLUDING LOCATION OF STRUCTURES AND APPURTENANCES) OR MODIFICATION IN USE, DESIGN WASTEWATER FLOW, OR WASTEWATER CHARACTERISTICS AS SPECIFIED IN THE ASSOCIATED IMPROVEMENT PERMIT AND APPLICATION, MAY SUBJECT THIS CONSTRUCTION AUTHORIZATION AND ASSOCIATED PERMIT(S) TO REVOCATION.

4. THIS CONSTRUCTION AUTHORIZATION AS PROVIDED IN G.S. 130A-335(f) AND G.S. 130A-336(b) SHALL BE VALID FOR A PERIOD EQUAL TO THE VALIDITY OF THE IMPROVEMENT PERMIT, NOT TO EXCEED 60 MONTHS.
   *CONSTRUCTION AUTHORIZATION EXPIRATION DATE: 1/5/2010

FEE: 300.00
DATE: 11/4/05

AUTHORIZATION FOR WASTEWATER SYSTEM CONSTRUCTION

ACS

PERMIT NUMBER: 5786B
PARCEL NUMBER: 195-211-43

JOB LOCATION ADDRESS: MAYHEW COUNTRY DRIVE, LOT 1
PROPERTY OWNER: LISA MACLELLAN
BUILDING CONTRACTOR: NA
SUBDIVISION NAME: MAYHEW COUNTRY ESTATES
AUTHORIZATION ISSUED BY: PHILO WALKER DATE: 11/07/05

DENR/DEH AUTHORIZED AGENT

AUTHORIZATION CONDITIONS

1. WASTEWATER SYSTEM CONSTRUCTION AND INSTALLATION MUST MEET ALL CONDITIONS AND SPECIFICATIONS AS SET FORTH IN IMPROVEMENT PERMIT NUMBER 5786B, AND THE ATTACHED SITE PLAN WITH SYSTEM DETAILS. CONSTRUCTION AND INSTALLATION MUST ALSO MEET ALL REQUIREMENTS SET FORTH IN THE RULES GOVERNING SANITARY SEWAGE COLLECTION, TREATMENT, AND DISPOSAL AND ANY OTHER APPLICABLE RULES AND LAWS.

2. AN *INSTALLATION, CONSTRUCTION, ALTERATION AND/OR REPAIR APPROVAL* MUST BE SECURED PRIOR TO INSTALLATION OF THE SEPTIC TANK SYSTEM. THE INSTALLER OF THE SYSTEM SHALL BE A REGISTERED SEPTIC TANK CONTRACTOR WITH THE MECKLENBURG COUNTY HEALTH DEPARTMENT.

3. ANY ALTERATION IN SITE OR SOIL CONDITIONS (INCLUDING LOCATION OF STRUCTURES AND APPURTENANCES) OR MODIFICATION IN USE, DESIGN WASTEWATER FLOW, OR WASTEWATER CHARACTERISTICS AS SPECIFIED IN THE ASSOCIATED IMPROVEMENT PERMIT AND APPLICATION, MAY SUBJECT THIS CONSTRUCTION AUTHORIZATION AND ASSOCIATED PERMIT(S) TO REVOCATION.

4. THIS CONSTRUCTION AUTHORIZATION AS PROVIDED IN G.S. 130A-335(f) AND G.S. 130A-336(b) SHALL BE VALID FOR A PERIOD EQUAL TO THE VALIDITY OF THE IMPROVEMENT PERMIT, NOT TO EXCEED 60 MONTHS.

5. OTHER CONDITIONS:
   AGREEMENT FORMS REQUIRED

MECKLENBURG COUNTY
LAND USE AND ENVIRONMENTAL SERVICES
Payment Receipt

Receipt Information

Date:	11/04/05	**Amount:**	150.00
Receipt #:	37906	**Tendered:**	150.00
Check / Auth #:	CHECK 1133	**Returned:**	0.00
Received By:	DAUGHVB		

Account Information

Account #: X38591
Contractor: MACLELLAN LISA
Attn:
Address: 7535 ELWOOD DR
Address:
City/State/Zip: CHARLOTTE, NC 28227

Item	Description	Permit#	Quantity	Unit Price	Total Price
0734	Auth for Waste Wtr Sys Constr 3321 MINTWOOD DR		1	150.00	150.00



Outstanding Balances

Month-To-Date	Prior Month	30 Days	60 Days	90 Days	Balance

MECKLENBURG COUNTY
LAND USE AND ENVIRONMENTAL SERVICES
Payment Receipt

Receipt Information


Date: 11/04/05
Receipt #: 37907
Check / Auth #: CHECK 1133
Received By: DAUGHVB

Amount: 150.00
Tendered: 150.00
Returned: 0.00

Account Information

Account #: X38591
Contractor: MACLELLAN LISA
Attn:
Address: 7535 ELWOOD DR
Address:
City/State/Zip: CHARLOTTE, NC 28227

Item	Description	Permit#	Quantity	Unit Price	Total Price
0703	Installation/Final Approval 3321 MINTWOOD DR		1	150.00	150.00



Outstanding Balances

Month-To-Date	Prior Month	30 Days	60 Days	90 Days	Balance

LD 143972

FOR REGISTRATION JUDITH A. GIBSON
REGISTER OF DEEDS
MECKLENBURG COUNTY, NC
2005 NOV 04 11:49 AM
BK:19590 PG:279-282 FEE:$20.00
INSTRUMENT # 2005222085
2005222085

STATE OF NORTH CAROLINA

COUNTY OF MECKLENBURG

WASTEWATER TREATMENT AND DISPOSAL SYSTEM DESIGN AGREEMENT: 15A NCAC 18A .1948 AND ANY OF THE FOLLOWING RULES: .1956; .1957(a); .1957(b); or .1957(c); OR .1969

FILE # 57866
PARCEL # 1952 1143

The undersigned, LISA L. Mackellan, owner of property located at 3321 Muirwood Drive, Mint Hill, (the "site") and described in an instrument recorded in Book 32 at Page 156, Mecklenburg Public Registry, hereby acknowledges that the undersigned applied to the Mecklenburg County Health Department (the "Department") for a permit to install a septic tank sewage disposal system on the site; that the Department evaluated the site for suitability for such a system in accordance with the regulations promulgated by the North Carolina Commission for Health Services as 15A NCAC 18A .1900 et seq.; that the Department originally classified the site as "unsuitable" pursuant to the standards set forth in the regulations; that the undersigned requested that the Department reclassify the site as "provisionally suitable" in light of the particular septic tank system proposed by the undersigned; that the Department considered various studies, data, and other information which indicate to the Department that the septic tank system proposed by the undersigned is allowed by the rules; and that the Department therefore reclassified the site as "provisionally suitable" and issued an appropriate permit for such proposed septic tank system.

The undersigned further acknowledges that the proper design, construction, operation and maintenance of such septic tank system is the responsibility of the designer, owner, developer, installer, or user of the system, as applicable, and that neither the Department nor its officials, employees, or agents warrant or guarantee that the said system installed pursuant to the permit issued by the Department will function in a satisfactory manner for any given period of time or that the Department, its officials, employees or agents assume any liability for any damages of any kind which are caused, or which may be caused, by a malfunction of such system.

The undersigned further acknowledges that the following conditions will apply to the site:

This instrument was prepared by: LISA L. Mackellan
Mail after recording to: 7535 ELWOOD DR. CHARLOTTE, NC 28227

- Any changes on the property may make the Improvement Permit null and void and may make the Improvement Permit subject to revocation.

- Do not grade, cut, fill, pave, construct a building or deck, dig a well, install a swimming pool or otherwise cover or disturb the soil (except for planting and maintaining grass or other ground covers) in a manner which will adversely affect the repair area or area where the septic tank system is located.

- When a private certified operator is required, no improvement permit for the designated repair shall be issued unless there is a private certified operator to carry out this management program in the service area where the proposed system is to be located. (Refer to Rule .1961, "Maintenance of Sewage Systems," for further information.)

- Additional fees will be required according to the Mecklenburg County user fee schedule applicable at the time for the issuance of a repair permit for any subsequent repairs to the sewage treatment and disposal system or for installation of a replacement system.

- At the time repairs to the sewage treatment and disposal system are to be made or a replacement system installed, the regulations in effect at that time will govern the repairs or installation of a replacement system.

The undersigned further agrees for himself, his heirs and assigns that he shall indemnify and hold harmless theDepartment, its employees, and officials, as well as Mecklenburg County and its employees and officials, for any damages or other claims of any person or persons whatsoever arising out of the installation, operation, or failure of said septic tank system.

Use of the singular masculine pronoun forms herein shall be deemed to also include the plural and feminine forms as the context may require.

This document shall be placed on the public records of the Register of Deeds of Mecklenburg County and indexed therein under the Grantor Index in the name or names of the undersigned, and the foregoing acknowledgements shall henceforth be binding on all persons claiming any right, title, or interest in the site.

IN WITNESS WHEREOF, the undersigned has hereunto set his hand and seal, or if corporate, has caused this instrument to be signed in its corporate name by its duly authorized officers and its seal to be hereunto affixed by authority of its Board of Directors, this 4 day of Nov 2005.

_____ (Corporate Name)

By: _____

_____ President

+ Lisa L. McLellan (SEAL)

+ Lisa L. McLellan (SEAL)

_____ (SEAL)

_____ (SEAL)

ATTEST:

_____

_____ Secretary

(Corporate Seal)

STATE OF NORTH CAROLINA
COUNTY OF Mecklenburg

I, MaryAnn Whalen, a Notary Public for said County and State, do hereby certify that Lisa Maclellan personally appeared before me this date and acknowledged the due execution of the foregoing instrument.

WITNESS my hand and notarial seal, this 4 day of Nov, 20 05

MaryAnn Whalen
Notary Public

My Commission Expires:

10·13·10

MARY ANN WHALEN NOTARY PUBLIC MECKLENBURG COUNTY, N.C.

STATE OF NORTH CAROLINA
COUNTY OF _____

I, _____, a Notary Public for said County and State, do hereby certify that _____ personally came before me this day and acknowledged that __he is _____ Secretary of _____, a North Carolina corporation, and that by authority duly given and as the act and deed of said corporation, the foregoing instrument was signed in its name by its _____ President, sealed with its corporate seal, and attested by _____ as its _____ Secretary.

WITNESS my hand and notarial seal, this _____ day of _____, 20___.

_____
Notary Public

My Commission Expires:

_____

REVISED 8-11-02

Nov 04 2005 1:34PM LUESA NORTH 704 432 2523 p.3

JUDITH A. GIBSON
REGISTER OF DEEDS, MECKLENBURG
COUNTY & COURTS OFFICE BUILDING
720 EAST FOURTH STREET
CHARLOTTE, NC 28202

PLEASE RETAIN YELLOW TRAILER PAGE

It is part of the recorded document, and must be submitted with original for re-recording and/or cancellation.

****

Filed For Registration:	**11/04/2005 11:49 AM**
Book:	**RE 19590 Page: 279-282**
Document No.:	**2005222085**
	PRMIT 4 PGS $20.00
Recorder:	**SERENA ROSS**

2005222085

CONDITIONS OF IMPROVEMENT PERMIT / CONSTRUCTION AUTHORIZATION

Permit Number: 5786B Tax Number: 195-211-43

- The IMPROVEMENT PERMIT is subject to revocation if site plans or the intended use change. There is to be NO grading, filling, or disturbance of the soil in the area of the septic tank system or repair area.
- CONSTRUCTION AUTHORIZATION must be obtained prior to receiving a Building Permit. The Construction Authorization is NOT transferable. Do not clear, grade, fill or disturb soil prior to obtaining a Construction Authorization.
- Domestic-type wastewater only. No industrial process wastewater may be discharged into the system.

Basement: ☐ Yes ☒ No ☐ Partial Basement

Primary Wastewater System

Type: ☐ I ☐ II ☐ III ☒ IV ☐ V ☐ VI

☐ Conventional
☒ Prefabricated, permeable block panel system
☐ Shallow Placed Conventional
☐ Low Pressure Pipe
☐ Large Diameter Pipe
☐ Fill
☐ Other
☐ Innovative or Experimental:

.25 Long-term acceptance rate (GPD/ft^2)	480 Max gallons/day wastewater flow	972 Absorption Area (ft^2)	9 Trench spacing (min. on centers) (ft)
Serviced by private well: ☐ Yes ☒ No	1600 Gallon septic tank	324 Total trench length (ft)	28 Maximum trench depth (in) (At least 12" of provisionally suitable soil must remain between trench bottom and unsuitable soil conditions.)
4 Bedrooms in residence	1000 Gallon pump tank	NA Depth of stone (in)	

Any surface water present: YES Type: BRANCH Minimum separation distance (ft):

Additional conditions: AGEEEMENT FORMS SHALL BE RECORDED AND ON FILE PRIOR TO CONSTRUCTION AUTHORIZATION RELEASE
TYPE IVa
KEEP THE SEPTIC SYSTEM <50 FEET FROM BRANCH
MUNICIPAL WATER

Repair Area System

Type: ☐ I ☐ II ☐ III ☒ IV ☐ V ☐ VI

☐ Conventional
☒ Prefabricated, permeable block panel system
☐ Shallow Placed Conventional
☐ Low Pressure Pipe
☐ Large Diameter Pipe
☐ Fill
☐ Other
☐ Innovative or Experimental:

972 Absorption Area (ft^2)	NA Depth of stone (in)	9 Trench spacing (min. on centers) (ft)	28 Maximum trench depth (in)
324 Total trench length (ft)			

The undersigned, an authorized agent of the MECKLENBURG COUNTY HEALTH DEPARTMENT, certifies that the Department has approved the Request for the Job Location contained in this document. The approval is granted in accordance with the provisions of Laws and Rules For Sewage Treatment and Disposal Systems in effect at the time of issuance of the permit and is subject to the following provisions:

*** No work shall be conducted on the septic tank system until an Installation, Construction, Alteration and/or Repair Approval is granted by this Department.

*** This Improvement permit is transferable.

Phillip A. Walker RS 11/5/05
DENR Authorized Agent Date

Owner/Agent Signature 11/4/05
Date

MECKLENBURG COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
700 N. TRYON ST., SUITE 211
CHARLOTTE, NC 28202
PHONE: (704) 336-5103
FAX: (704) 336-6894

NC DENR
DIVISION OF ENVIRONMENTAL HEALTH
ON-SITE WASTEWATER SECTION

IWWS-100195

Nov 04 2005 4:14PM LUESA NORTH 704 432 2523 p.1

CONDITIONS OF IMPROVEMENT PERMIT / CONSTRUCTION AUTHORIZATON

Permit Number: **5786B** Tax Number: **195-211-43**

- The IMPROVEMENT PERMIT is subject to revocation if site plans or the intended use change. There is to be **NO** grading, filling, or disturbance of the soil in the area of the septic tank system or repair area.
- CONSTRUCTION AUTHORIZATION must be obtained prior to receiving a Building Permit. The Construction Authorization is **NOT** transferable. Do not clear, grade, fill or disturb soil prior to obtaining a Construction Authorization.
- Domestic-type wastewater only. No industrial process wastewater may be discharged into the system.

Basement: ☐ Yes ☒ No ☐ Partial Basement

Primary Wastewater System

Type: ☐ I ☐ II ☐ III ☒ IV ☐ V ☐ VI

☐ Conventional
☒ Prefabricated, permeable block panel system
☐ Shallow Placed Conventional
☐ Low Pressure Pipe
☐ Large Diameter Pipe
☐ Fill
☐ Other
☐ Innovative or Experimental:

.25 Long-term acceptance rate (GPD/ft^2)	480 Max gallons/day wastewater flow	972 Absorption Area (ft^2)	9 Trench spacing (min. on centers) (ft)
Serviced by private well: ☐ Yes ☒ No	1500 Gallon septic tank	324 Total trench length (ft)	28 Maximum trench depth (in) (At least 12" of provisionally suitable soil must remain between trench bottom and unsuitable soil conditions.)
4 Bedrooms in residence	1000 Gallon pump tank	NA Depth of stone (in)	

Any surface water present: **YES** Type: **BRANCH** Minimum separation distance (ft):

Additional conditions: **AGEEEMENT FORMS SHALL BE RECORDED AND ON FILE PRIOR TO CONSTRUCTION AUTHORIZATION RELEASE**
,TYPE IVa
KEEP THE SEPTIC SYSTEM <50 FEET FROM BRANCH
MUNICIPAL WATER

Repair Area System

Type: ☐ I ☐ II ☐ III ☒ IV ☐ V ☐ VI

☐ Conventional
☒ Prefabricated, permeable block panel system
☐ Shallow Placed Conventional
☐ Low Pressure Pipe
☐ Large Diameter Pipe
☐ Fill
☐ Other
☐ Innovative or Experimental:

972 Absorption Area (ft^2)	NA Depth of stone (in)	9 Trench spacing (min. on centers) (ft)	28 Maximum trench depth (in)
324 Total trench length (ft)			

The undersigned, an authorized agent of the MECKLENBURG COUNTY HEALTH DEPARTMENT, certifies that the Department has approved the Request for the Job Location contained in this document. The approval is granted in accordance with the provisions of Laws and Rules For Sewage Treatment, and Disposal Systems in effect at the time of issuance of the permit and is subject to the following provisions:

*** No work shall be conducted on the septic tank system until an Installation, Construction, Alteration and/or Repair Approval is granted by this Department.

*** This Improvement permit is transferable.

Philo A. Walker RS 1/5/05
DENR Authorized Agent Date

See attachment
Owner/Agent Signature Date

MECKLENBURG COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
700 N. TRYON ST., SUITE 211
CHARLOTTE, NC 28202
PHONE: (704) 336-5103
FAX: (704) 336-6894

NC DENR
DIVISION OF ENVIRONMENTAL HEALTH
ON-SITE WASTEWATER SECTION

Residential Subsurface Wastewater Treatment and Disposal System Design

for

Lot 1 - Mayhew Country Estates
3321 Mintwood Drive
Mint Hill, North Carolina


Tax Parcel # 195-211-43
December 10, 2004

Prepared for:

Mrs. Audrey Mayhew
3362 Mayhew Forest Drive
Charlotte, NC 28227

Prepared by:

Larry Thompson, RS, PWS
114 Orchard Ridge Road
Locust, NC 28097-8748
Phone: 704-301-4881
Fax: 704-888-1496
larry@thompsonenv.com



CC: Mr. Philo Walker, RS
Mecklenburg County Environmental Health

Details

In an application for an Improvement Permit filed with the Mecklenburg County Health Department (MCHD) by Mrs. Audrey Mayhew, November 18, 2004, the subject property was proposed to be developed with a single family 4-bedroom residence served by a private well. Based upon this information, a soil and site evaluation was conducted by the MCHD where the 0.918 acre lot was determined to be "Unsuitable" for the installation of a subsurface wastewater treatment and disposal system in accordance with the *Laws and Rules for Sewage Treatment, and Disposal Systems* 15A NCAC 18A .1900 (North Carolina Department of Environment and Natural Resources, Division of Environmental Health, On-Site Wastewater Section).

Upon further investigation by Thompson Environmental Consulting, Inc. (TEC), it was determined that municipal water is available, eliminating the need for a private well, and that a limited area of "Suitable" Group IV soils are located parallel to Mintwood Road (northwest boundary), which would allow for the installation of a pressure-dosed pre-fabricated permeable block panel system (PPBPS) for a 4-bedroom residence. It is the desire of the owner that the MCHD consider reclassifying this lot as "Suitable", allowing for the issuance of a Construction Authorization, based upon the following proposal.

Location

The subject property is located in Mayhew Country Estates (Lot 1 physical address: 3321 Mintwood Drive) in the town of Mint Hill, North Carolina. Traveling southwest on NC 51 out of Mint Hill, turn left on Mintwood Drive. The Lot 1 is located on the right at the intersection of Mintwood Drive and Mayhew Country Drive.

References

Laws and Rules for Sewage Treatment and Disposal Systems, 15A NCAC 18A, Section .1900, Department of Environment and Natural Resources, Division of Environmental Health, On-Site Wastewater Section, August 17, 2000.

Design, Installation and Maintenance of the T & J Panel Wastewater Treatment System; Sixth Edition, published by T & J Panel.

Design and Installation of Low Pressure Pipe Wastewater Treatment Systems; by Craig Cogger, Bobby Carlisle; Dennis Osborne and Ed Holland. Published by UNC Sea Grant College Pub. UNC-SC-82-03, May 1982.

Onsite Wastewater Treatment and Disposal Systems; EPA 625/R-00/008 Design Manual, February 2002.

Plans and Specifications

Septic Tank

- The septic tank shall be State approved (Section .1953 of 15A NCAC 18A), watertight, structurally sound and 1500 gallons in capacity.
- The septic tank will be fitted with an approved effluent filter and riser for easy access and periodic maintenance.
- It is the responsibility of the septic contractor to thoroughly inspect the septic tank prior to accepting delivery, thereby assuring that the tank has had time to properly cure and is not cracked or "honey combed".

Pump Tank

- The pump tank shall be State approved, of one-piece construction, watertight, structurally sound and 1000 gallons in capacity. Again, it is the responsibility of the septic tank contractor to thoroughly inspect each pump tank prior to accepting delivery.
- The pump tank shall have access risers that extend, at a minimum, 6 inches above finished grade and must have less than 36 inches of fill over its top once finished grade has been established (a reinforced concrete tank will be required if finished soil cover is 36 inches or greater in depth).
- The pump and alarm controls shall be provided with manual circuit disconnects within a watertight, corrosion resistant, Nema 4X rated control panel. The control panel must be securely mounted outside, adjacent to the pump tank riser and at a minimum of 12 inches above finished grade. Pump and float control wiring should be long enough to reach from the tank to the control panel without splicing, routed through wire conduit, and sealed at the openings within the pump tank as well as the control panel enclosure. It is paramount that the conduit is properly sealed to prevent the escape of flammable gases from the pump tank. Furthermore, there must be two electrical circuits for the pump tank controls: one for the pump and one for the alarm controls.
- The pump tank shall have a properly functioning high water alarm incorporated into the control panel. The alarm circuit shall be supplied separate from any pump overload and short circuit devices. The alarm shall be both audible and visible by the system users.
- The float switch for the high water alarm should be mounted at a location slightly above the "pump on" elevation for the pump float control switch. The high water alarm float switch shall not be set more than 3 inches above this elevation.
- Pump float(s) shall be mounted so that the effluent at the end of a pump cycle is above the top of the effluent pump. The septic contractor must determine pump draw down and set the float switch accordingly.
- Float switch tie downs must be made of a corrosion resistant material. Do not use electrical tape or metal hose clamps to secure these switches. Floats should be

mounted on a separate "float tree" rather than the pump supply line (see pump tank detail).
- The pump must be placed on two 4-inch concrete blocks to allow for some settling of solid particulates within the pump tank.

Pump Tank Effluent

- The pump discharge piping, to the pre-treatment units, shall be fitted with a pressure effluent filter. The filter must be equivalent to the GAG Sim Tech Filter, Boyne City, Michigan, 49712, and telephone: 1-888-999-3290. This device provides a very high degree of filtration and is highly recommended.

Pipe and Fittings

- All discharge piping, supply lines, valves and disconnects should be made of PVC.
- All joints must be properly "welded" utilizing the appropriate PVC cement for each application.
- The supply line from the pump tank to the pressure manifold shall be 2 inch Schedule 40 PVC (approximate length of supply line is 100 feet).
- The lateral distribution lines shall be 1 ¼ inch Schedule 40 PVC. Holes in the laterals should be drilled on site and at the 10 and the 2 o'clock position (one hole per panel). Lateral hole size is 5/32 of an inch.
- There shall be a threaded PVC union above each pump to facilitate easy removal of the pumps for maintenance or replacement.
- The end of each lateral is to be provided with a "turn up", contained within a turf/gate valve box, that provides above ground access for periodic clean out and pressure head adjustment. Utilize (2) 45-degree elbows rather than one 90-degree elbow for each turn up to make future cleaning easier.

Supply Manifold

- The control valves (gate valves) for each lateral distribution line shall be contained within one manifold box/vault of adequate size. The box should be placed upon a gravel base.
- The supply manifold conveys effluent from the pump to the lateral distribution lines.
- The supply manifold should be constructed by connecting a series of (3) 2" x 2" x 1 ¼" tees to the 2 inch supply line (see pressure manifold detail).

Backfill

- Backfill sand shall be naturally occurring, washed, and falls within the gradation of ASTM C-33 specification (used in the ready mix industry and is readily available).

Drainfield Installation

- The drainfield has been previously laid out on-site utilizing metal stemmed flags. Once this area has been approved by the MCHD, the property owner/builder should mark this area and isolate it as much as possible from construction traffic. Prior to the system installation, the septic contractor shall contact the MCHD and the system designer for a preconstruction conference at which time the drainfield area will be re-verified.
- Under no circumstances shall any construction take place within the drainfield area while the soil is in a wet condition. If the installer has doubts as to whether or not the drainfield area is dry enough to begin construction, the Mecklenburg County Health Department should be contacted for permission to proceed with the installation.
- The specified system is a Type IVa, pressure dosed, pre-fabricated permeable block panel system – specifically the 16 inch high panel system manufactured by T&J Panel Wastewater Treatment System, Patent No. 4013559; telephone: 1-800-222-2577. The installer must follow the manufacturer's guidelines for installing the T&J Panel System and should request an installation manual from the manufacturer prior to beginning construction.
- The initial drainfield consists of (6) lateral trenches to be constructed 3 feet wide by 54 feet in length. It is essential that the lateral trenches be constructed on contour with the land, with each trench being excavated level from beginning to end. The use of a tripod mounted engineer's level is essential to assure that each trench is constructed as level as possible.
- The maximum trench depth for this system shall be 28 inches and each trench shall be placed on a minimum of 9 foot on centers.
- Once trenches are dug, the side walls shall be raked and a light dusting of lime applied.
- Backfill the trench with 6 inches of sand and level to grade. Once leveled, place 1 x 4 or 6 inch boards on top of the sand the entire length of each trench. Once the grade boards have been set, the panels may be set into the trench. The panels should be placed 6 inches apart.
- Once the panels have been set, line the top chamber of each panel with 10 – 12 pounds of clean particle sand (medium sand blasting sand). Coverage depth should be approximately 1 inch thick. *Please note that this sand is not the same material specified for backfill.*
- Tar seal rope should be placed in the "U" outs of each end of the panel to form seals. Once the tar rope is in place, the 1 ¼ inch Schedule 40 PVC laterals can be added and the seal completed by the addition of more tar rope on the top and sides of the pipe. Now that the connection and seals are complete, a block cap is placed on each end of the panel so that all openings are covered.
- The end of each lateral should be fitted with a short turn up consisting of (2) 45-degree elbows topped by a threaded female coupling with cap. Each turn up must be fitted with a turf/gate valve box with lid fitted flush to finished grade.
- Once the lateral has been installed and the panels closed, the trench is ready to be backfilled to the top with the sand used in the trench bottom. At this point, the trenches should be left open for the final inspection by the MCHD.

Proper Operation Check

- After all components of the waste water disposal system have been installed and connected, the system shall be checked for proper operation.
- With the electrical power turned off, fill the pump tank with water until the liquid rises to a level high enough to activate the high water alarm float. Turn on the electrical power. The alarm, alarm light and pump should activate at this time. Turn off the electrical power once these checks have been performed and prepare to set the head pressure at the manifold box.

Pressure Head Adjustment

- The pressure head must be adjusted to match the design specifications. The pressure head is measured by the height of the liquid coming from the turn ups at the end of each lateral when the pump is running (utilizing stand pipes).
- Prepare a length of pipe (stand pipe), cut to the desired head pressure height and fitted with a threaded adapter that will screw into the turn up couplings at the end of each lateral. Thread the stand pipes into each lateral and then turn the power on to the pump, allowing the water to rise within the stand pipes. Adjust the gate valves within the supply manifold box to achieve the specified head pressure (liquid height in the stand pipes should equal the design head pressure).
- Once the pressure head has been adjusted, allow the pump to run through the remainder of the cycle. The pump float switch will automatically turn the pump off if it is operating properly. Make sure that the effluent pump is completely submerged in the remaining water, making adjustments to the float switch(es) as needed. This completes the checks for proper operation of the pump, alarm and float switches.
- At this point, the standpipes may be removed and replaced with the threaded turn up caps.

Final Landscaping

- The drainfield shall be shaped to shed rainwater and be free from low spots.
- The entire area of the drainfield should be planted with grass as soon as possible to prevent erosion. The soil should be properly tilled, limed (if necessary) and fertilized prior to planting. After applying grass seed, the area should be heavily mulched with straw or other suitable material.

Utility Conflicts

- The builder and property owner must take special care in planning for water, power, gas, telephone and cable lines. These utilities shall be kept clear of all parts of the septic system and its proposed repair area. Improper planning for underground utilities can negatively impact the installation and, in some cases, cause irreparable damage. If there are any questions regarding preferred routes, contact the MCHD as soon as possible.

Well Location

- As previously mentioned, municipal water is available for this lot. If a private well is to be installed as a water supply source, the well must be placed as far as is feasible from any of the septic system components but, in no case, less than 50 feet from any part of the septic system.

Maintenance

Operation and Maintenance

The designed system is classified as a Type IVa wastewater treatment and disposal system and will require ongoing maintenance. State regulations require that a system of this type be managed by a person certified (Certified Subsurface System Operator) by the North Carolina Department of Environment and Natural Resources to operate subsurface wastewater systems (Section .1961 Maintenance of Sewage Systems). A "Maintenance Contract" between the system owner and a Certified Operator will be required by the MCHD prior to the issuance of a final system approval or Operation Permit.

- The minimum inspection/maintenance and reporting frequency for a Type IVa system is twice a year by the Certified Operator. The local health department is required to inspect the system once every three years.
- The septic and pump tanks shall be pumped every 4 years or when the solids within the septic tank reach an elevation that is equivalent to 1/3 of the volume of the tank. In some situations, the tanks may need to be pumped more frequently; for example, if you are using a garbage disposal, it is recommended that the septic and pump tanks be cleaned out annually. Regardless, the Certified Operator will be able to advise when it is necessary to pump out tank solids.
- Pressure head for laterals should be checked and adjusted semi-annually, flushing with clean water as necessary to remove any accumulated solids.
- The effluent filters should be inspected semi-annually. When it becomes necessary to clean the effluent filters, the filters should be removed and the accumulated debris washed back into the septic or pump tank – not onto the lawn.
- All piping and valves should be inspected semi-annually for damage and corrections/repairs made immediately.
- The pump and float controls/switches should be inspected semi-annually to assure proper operation
- The drainfield area should be maintained to prevent over growth of vegetation. Any damp areas, leakages or malfunctions should be addressed immediately.
- Divert gutter downspouts and surface water runoff away from the septic and pump tanks.

Suggestions to the Homeowner

- As previously mentioned, if you plan to use a garbage disposal in your home you should plan to have your septic and pump tanks cleaned out annually. The ground up garbage adds large amounts of solids into a septic tank that tend to degrade at a very slow rate.
- Grease, cooking oils, coffee grounds and non-degradable solids (disposable diapers, cigarettes and solid paper wastes) should never be put into a septic tank.
- Used motor oil or any oily liquids should not be disposed of in a septic tank.
- Be aware of the amount of water that you are using in your home. Water saving fixtures and devices can be installed on sinks, toilets and showers to reduce the volume of wastewater that you are sending to your drainfield.
- Run dishwashers and washing machines only when you have a full load.
- Use liquid detergents. Powdered detergents have binding agents in them that tend to solidify in the wastewater disposal system.
- Repair leaky faucets and toilets. Small drips equal large volumes of water over time and can over burden your drainfield.
- Do not use chemical additives in your system. Various studies have indicated that they do not increase the biological activity that naturally occurs in the septic system and, in some cases, certain additives have been found to be detrimental to the life of a system.
- It is a good idea to post the contact information of the Certified Operator for your system somewhere within the house. In the event of a "High Water Alarm", you will want to contact the Operator for proper instruction as well as to request that an emergency inspection be performed.
- Finally, taking good care of your septic system will help to assure that you experience years of trouble free service at a relatively low cost. On-site wastewater treatment and disposal is still the most environmentally friendly method of treating residential/commercial waste and you should keep your system in use for as long as it is properly functioning! If you have additional questions, please feel free to contact your system designer or the MCHD.


Design Specifics


Lot 1 – Mayhew Country Estates

Daily Design Flow:	480 GPD – 4 bedroom house
Septic Tank Size:	1500 gallons (2 compartments)
Pump Tank Size:	1000 gallons (one piece)
Effluent Loading Rate:	Design = 0.25 GPD per sq. ft. (50 % reduction for the PPBPS)
Supply Length and Diameter:	Approx. 100 feet of 2 inch Sch. 40 PVC (please see note at the bottom of this page.)
Number and Size of Laterals:	(6) 1 1/4 inch x 54 foot laterals
Hole Size:	5/32 inch
Hole Spacing:	1 per panel = 72 total
Dosing Volume:	259.2 gallons per dose
Flow Rate Through System:	25.42 gallons per minute
Elevation Head:	17.0 feet (may vary, please see note at the bottom of this page)
Pressure Head:	2 feet
Pump Requirements:	29.52 GPM at 17.0 feet of head
Depth of Water Pumped:	12.3" (J&S STB-97-1000 used) check with individual tank manufacturer (1 cu. Ft. of water equals 7.5 gal.)
Pump Run:	10.2 minutes
Check Valve:	Yes
Vapor Lock Hole:	Yes (A vapor lock hole can reduce vibrations in the discharge pipe upon start up and shut down)

* Please note that supply line and elevation head measurements are approximate. It is the contractor's responsibility to confirm these values based upon the actual house and plumbing location. If there is a discrepancy, contact the system designer prior to beginning construction.

CURVE TABLE				
CURVE	LENGTH	RADIUS	BEARING	CHORD
C1	28.28'	20.00'	N 15°40'29" E	25.98'





COMMENTS

- 1500 Gallon Septic Tank
- 1000 Gallon Pump Tank
- Drainlines to be installed 3 feet wide, 28 inches deep, 9 foot on center.
- Keep trench bottoms level from beginning to end.

NOTE:
ALL CORNERS ARE I.PIN(F) UNLESS OTHERWISE NOTED.

NOTE:
ALL DISTANCES ARE HORIZONAL DISTANCES UNLESS OTHERWISE NOTED.

NOTE:
AREA BY COORDINATE COMPUTATION.

NOTE:
PROPERTY SUBJECT TO ANY VALID & ENFORCEABLE EASEMENTS, RESTRICTIONS & RIGHTS OF WAY OF RECORD.

SUBJECT PROPERTY IS NOT LOCATED IN A SPECIAL FLOOD HAZARD AREA AS DETERMINED BY FLOOD INSURANCE RATE MAP.

NOTE:
THIS PLAT IS OF A SURVEY OF AN EXISTING PARCEL or PARCELS OF LAND.

Location Map
(Not To Scale)

Tax Parcel:

E.C. = 1' : 10,000' •

Deed Ref:
Map Book: 32 / 156

Plot Plan
For

Audrey Mayhew

Lot 1, Mayhew Country Estates, Map 1

Mecklenburg County
Mint Hill, N.C.

Drawing No. 355-04


Scale: 1" = 50'

July 2, 2004


Thompson Environmental Consulting, Inc.
114 Orchard Ridge Road
Locust, NC 28097-8748

Location: LOT 1 Mayhew Corky Estates

Date:




CUTAWAY OF PRESSURE PANEL



Thompson Environmental Consulting, Inc.
114 Orchard Ridge Road
Locust, NC 28097-8748

Location: Lot 1 Mayhew Country Estates

Date:



GOULDS PUMPS



Submersible Effluent Pump

MODEL 3885

WE Series

PROSURANCE AVAILABLE FOR RESIDENTIAL APPLICATIONS.

APPLICATIONS

Specifically designed for the following uses:

- Homes
- Farms
- Trailer courts
- Motels
- Schools
- Hospitals
- Industry
- Effluent systems

SPECIFICATIONS

Pump

- Solids handling capabilities: ¾" maximum.
- Discharge size: 2" NPT.
- Capacities: up to 140 GPM.
- Total heads: up to 128 feet TDH.
- Temperature: 104°F (40°C) *continuous* 140°F (60°C) intermittent.
- See order numbers on reverse side for specific HP, voltage, *phase and RPM's* available.

FEATURES

■ **Impeller:** Cast iron, semi-open, non-clog with pump-out vanes for mechanical seal *protection. Balanced for* smooth operation. Silicon bronze impeller available as an option.

■ **Casing:** *Cast iron volute type* for maximum efficiency. 2" NPT discharge.

■ **Mechanical Seal: SILICON CARBIDE VS. SILICON CARBIDE** sealing faces. Stainless steel metal parts, BUNA-N elastomers.

■ **Shaft:** Corrosion-resistant, stainless steel. Threaded design. Locknut on all models to guard against component damage on accidental reverse rotation.

■ **Fasteners:** 300 series stainless steel.

■ Capable of running dry without damage to *components.*

■ Designed for continuous operation when fully submerged.

MOTORS

■ Fully submerged in high-grade turbine oil for lubrication and efficient heat transfer.

■ Class B insulation on ⅓-1½ HP models.

■ Class F insulation on 2 HP models.

Single phase (60 Hz):

- Capacitor start motors for maximum starting torque.
- Built-in overload *with* automatic reset.
- SJTOW or STOW severe duty oil and water resistant power cords.
- ⅓ and ½ HP models have NEMA three prong grounding plugs.
- ¾ *HP and larger units have* bare lead cord ends.

Three phase (60 Hz):

- Class 10 overload protection must be provided in separately ordered starter unit.
- STOW power cords all have bare lead cord ends.

■ **Designed for Continuous Operation:** Pump ratings are within the motor manufacturer's recommended working limits, can be operated continuously without damage when fully submerged.

■ **Bearings:** Upper and lower heavy duty ball bearing construction.


■ **Power Cable:** Severe duty rated, oil and water resistant. Epoxy seal on motor end provides secondary moisture barrier in case of outer jacket damage and to prevent oil wicking. Standard cord is 20'. Optional lengths are available.

■ **O-ring:** Assures positive sealing against contaminants and oil leakage.

AGENCY LISTINGS

Tested to UL 778 and CSA 22.2 108 Standards By Canadian Standards Association File #LR38549

Goulds Pumps is ISO 9001 Registered.



Goulds Pumps

ITT Industries

© 2003 Goulds Pumps
Effective July, 2003
B3885

www.goulds.com

GOULDS PUMPS


Submersible Effluent Pump

MODEL 3885

WE Series

COMPONENTS

Item No.	Description
1	Impeller
2	Casing
3	Mechanical Seal
4	Motor Shaft
5	Motor
6	Ball Bearings
7	Power Cable
8	Casing O-Ring



MODELS


Order No.	HP	Volts	Phase	Max. Amp.	RPM	Solids	Wt. (lbs.)
WE0311L	⅓	115	1	10.7	1750	¼"	56
WE0318L		208		6.8			
WE0312L		230		4.9			
WE0311M		115		10.7			
WE0318M		208		6.8			
WE0312M		230		4.9			
WE0511H	½	115	1	14.5	3500		60
WE0518H		208		8.1			
WE0512H		230		7.3			
WE0538H		200	3	4.9			
WE0532H		230		3.3			
WE0534H		460		1.7			
WE0537H		575		1.4			
WE0511HH		115	1	14.5			
WE0518HH		208		8.1			
WE0512HH		230		7.3			
WE0538HH		200	3	4.9			
WE0532HH		230		3.6			
WE0534HH		460		1.8			
WE0537HH		575		1.5			
WE0718H	¾	208	1	11.0			70
WE0712H		230		10.0			
WE0738H		200	3	6.2			
WE0732H		230		5.4			
WE0734H		460		2.7			
WE0737H		575		2.2			
WE1018H	1	208	1	14.0			
WE1012H		230		12.5			
WE1038H		200	3	8.1			
WE1032H		230		7.0			
WE1034H		460		3.5			
WE1037H		575		2.8			
WE1518H	1½	208	1	17.5			80
WE1512H		230		15.7			
WE1538H		200	3	10.6			
WE1532H		230		9.2			
WE1534H		460		4.6			
WE1537H		575		3.7			
WE1518HH		208	1	17.5			
WE1512HH		230		15.7			
WE1538HH		200	3	10.6			
WE1532HH		230		9.2			
WE1534HH		460		4.6			
WE1537HH		575		3.7			
WE2012H	2	230	1	18.0			83
WE2038H		200	3	12.0			
WE2032H		230		11.6			
WE2034H		460		5.8			
WE2037H		575		4.7			

PERFORMANCE RATINGS (gallons per minute)

Order No.		WE03L	WE03M	WE05H	WE07H	WE10H	WE15H	WE05HH	WE15HH	WE20H
Total Head Feet of Water	HP	⅓	⅓	½	¾	1	1½	½	1½	2
	RPM	1750	1750	3500	3500	3500	3500	3500	3500	3500
	5	86	–	–	–	–	–	–	–	–
	10	70	63	78	–	–	–	58	–	–
	15	52	50	70	90	–	–	53	–	–
	20	27	35	60	83	98	123	49	90	136
	25	–	–	48	76	94	117	45	87	133
	30	–	–	35	67	88	110	40	83	130
	35	–	–	20	57	82	103	35	80	126
	40	–	–	–	45	74	95	30	77	121
	45	–	–	–	35	64	86	25	74	116
	50	–	–	–	25	53	77	–	70	110
	55	–	–	–	–	40	67	–	66	103
	60	–	–	–	–	30	56	–	63	96
	65	–	–	–	–	20	45	–	58	89
	70	–	–	–	–	–	35	–	55	81
	75	–	–	–	–	–	25	–	51	74
	80	–	–	–	–	–	–	–	47	66
	90	–	–	–	–	–	–	–	37	49
	100	–	–	–	–	–	–	–	28	30

DIMENSIONS

(All dimensions are in inches. Do not use for construction purposes.)



Goulds Pumps and the ITT Engineered Blocks Symbol are registered trademarks and tradenames of ITT Industries.

PRINTED IN U.S.A.

SPECIFICATIONS ARE SUBJECT TO CHANGE WITHOUT NOTICE.

Goulds Pumps

ITT Industries

FEE: 225
DATE: 11/15/04
Check 3411 OKIA

APPLICATION FOR IMPROVEMENT PERMIT
FOR RESIDENTIAL SITE
INDIVIDUAL WATER AND WASTEWATER
SYSTEMS PROGRAM

[ ] CRT

TYPE APPLICATION: ✓ NEW SYSTEM ___ EXPANSION/ ALTERATION OF EXISTING SYSTEM ___ REPAIR OF EXISTING SYSTEM

NORTH CAROLINA
DEPARTMENT OF ENVIRONMENT,
HEALTH, AND NATURAL RESOURCES
DIVISION OF ENVIRONMENTAL HEALTH
ON-SITE WASTEWATER SECTION

FILE #: 5198(2)

PROPERTY INFORMATION (FROM ENGINEERING FORM) FOR JOB LOCATION:

TAX/PARCEL NUMBER: 195-211-39 00

STREET ADDRESS: Mayfair Country Drive

SUBDIVISION OR MOBILE HOME PARK NAME: Mayfair Country Estate

LOT NUMBER: 1

TYPE OF BUILDING (CHECK ONE):

___ SINGLE MOBILE HOME(S)
___ DOUBLE WIDE (D)
X HOUSE (H)
___ MODULAR HOME (M)
___ MULTIPLE FAMILY (U)
___ OTHER (O)

TOWNSHIP (CHECK ONE):

✓ 0 MECKLENBURG
___ 1 CHARLOTTE
___ 2 DAVIDSON
___ 3 CORNELIUS
___ 4 PINEVILLE
___ 5 MATTHEWS
X 6 HUNTERSVILLE
X 7 MINT HILL

195-211-43

HEATED SQUARE FOOTAGE:

NUMBER OF BEDROOMS: 4

NUMBER OF OCCUPANTS:

CLOSING DATE

533' 25% Red .25%
711 con

.92

COPY

FOUNDATION FOR RESIDENCE:

___ WITHOUT BASEMENT
___ ON SLAB
___ CRAWL SPACE
___ WITH BASEMENT /PLUMBING
___ WITH BASEMENT /NO PLUMBING

IF EXPANSION/ALTERATION OF EXISTING SYSTEM, DESCRIBE THE PROPOSED BUILDING ADDITION:

WILL THERE BE A HOME BUSINESS IN THE RESIDENCE: ___ YES X NO TYPE: _____

WATER SUPPLY (CHECK ONE):
Well or City water
___ COMMUNITY (C)
___ SHARED WELL (S)
___ MUNICIPAL (M)
___ OTHER 'SPRINGS' (O)
X PRIVATE WELL (P)

IF ANY OF THE FOLLOWING ARE LOCATED ON THE PROPERTY, PLEASE SHOW LOCATION ON PLAT:

BURIED CABLES, LANDFILLS, STUMPHOLES ___ YES ✓ NO
EXISTING WASTEWATER SYSTEMS ___ YES ✓ NO
EASTMENTS OR RIGHT-OF-WAYS ✓ YES ___ NO
WELL, SPRINGS OR WATERLINES ___ YES ✓ NO
DESIGNATED WETLANDS ? ✓ YES ___ NO

3362 Mayhew Entrance Lane

PROPERTY OWNER:	LEGAL AGENT FOR PROPERTY OWNER, IF APPLICABLE:
NAME: Mayhew Audrey III (LAST) (FIRST) (MI)	NAME: (LAST) (FIRST) (MI)
ADDRESS: 5453241	DAYTIME PHONE: ( ) —
CITY: Charlotte STATE: N.C ZIP:	
DAYTIME PHONE: 704 5453241	

WHAT DATE WAS THE PROPERTY ORIGINALLY DEEDED AND RECORDED? 1965

An Improvement Permit is subject to suspension or revocation if site plans or the intended use change or if information submitted in this application is falsified or changed. The undersigned, owner, or legal agent for the owner, of the property described above as the "Job Location" has read the foregoing application, acknowledges that the contents of same are true, and authorizes agents of the Mecklenburg County Health Department to enter onto the property for the purpose of processing this request.

SIGNED: Audrey Mayhew DATE: 11-10-04


MECKLENBURG COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
c/o HAL MARSHALL CTR., SUITE 211, 700 N. TRYON ST., CHARLOTTE, N.C. 28202., (704) 336-5102

CURVE TABLE				
CURVE	LENGTH	RADIUS	BEARING	CHORD
C1	28.28'	20.00'	N 15°40'29" E	25.98'

File # 57868
TC #195-211-39P0

Parcel 195-211-39

Plat



Surveyor's Area drawn in Layout Building

COPY

Department of Environment, Health and Natural [illegible]
Division of Environmental Health
On-site Wastewater Section

Property ID: 195-211-43
Lot #: 1
File #: 5786B
Code: 2

SOIL/SITE EVALUATION
for ON-SITE WASTEWATER SYSTEM

Owner: Audrey W. Mayhew
Address: 3362 Mayehw Forrest Lane, Charlotte, N. C., 28227
Proposed Facility: Residence
Design Flow (.1949): 480gpd
Location of Site: Mayhew Country Drive
Water Supply: [ ] Public [x] Individual [x] Well [ ] Spring [ ] Other
Evaluation Method: [x] Auger Boring [ ] Pit [ ] Cut
Type of Wastewater: [x] Sewage [ ] Industrial Process [ ] Mixed

Applicant:
Date Evaluated: 11/22/2004
Property Size: .92a
Property Recorded:

PROFILE #	1940 Landscape Position/ Slope%	1940 Horizon Depth (IN.)	SOIL MORPHOLOGY 1941 1941 Structure/ Texture	1941 Consistence/ Mineralogy	OTHER PROFILE FACTORS 1942 Soil Wetness/ Color	1943 Soil Depth (IN.)	1956 Sapro Class	1944 Restr Horiz	Profile Class & LTAR
1	LS, 10	0-4	GR/CL	FR/SEXP/SS/SP	2.5Y7/1@24"	27+	N/A	NONE	US, IV
		4-23	SBK/C	FI/SEXP/S/P					
		23-27	SBK/CL	FR/SEXP/SS/SP					
2	"	0-6	GR/CL	"	"	32+	"	"	US
		6-15	SBK/C	FI/SEXP/S/P					
		15-32	ABK/C	VFI/EXP/VS/VP					
3	"	0-3	GR/CL	FR/SEXP/SS/SP	2.5Y7/1@32"	36+	"	"	"
		3-24	SBK/C	FI/SEXP/S/P					
		24-36	ABK/C	VFI/EXP/VS/VP					
4	"	0-4	GR/CL	FR/SEXP/SS/SP	2.5Y7/1@33"	37+	"	"	"
		4-27	SBK/C	FI/SEXP/S/P					
		27-37	ABK/C	VFI/EXP/VS/VP					
5	LS, 6	0-4	GR/CL	FR/SEXP/SS/SP	>39" TO SOIL WETNESS	39	"	"	PS, IV .225GPD/FT^2
		4-36	SBK/ABK/C	FI/SEXP/S/P					
		36-39	ABKPL/C	"					
6	"	0-3	GR/CL	FR/SEXP/SS/SP	>48" TO SOIL WETNESS	48	"	"	PS, IV .275GPD/FT^2
		3-48	SBK/ABK/C	FI/SEXP/S/P					
7	"	0-2	GR/CL	FR/SEXP/SS/SP	"	"	"	"	PS, IV .25GPD/FT^2
		2-48	SBK/ABK/C	FI/SEXP/S/P					

Description	Initial System	Repair System
Available Space (.1945)	PS	US
System Type(s)		
Site LTAR	.25GPD/FT^2	.25GPD/FT^2

Other Factors (.1946):
Site Classification (.1948): UNSUITABLE
Evaluated By: W. R. Martin, LSS, 11/23/2004 W. R. Martin
Others Present:


COMMENTS:
100% repair

FILE #: 5786B

Landscape Position	Group	Texture	.1955 LTAR	Structure
R-Ridge	I	S-Sand	1.2 - 0.8	SG-Single Grain
SS-Shoulder Slope		LS-Loamy Sand		M-Massive
LS-Linear Slope				CR-Crumb
FS-Food Slope	II	SL-Sandy Loam	0.8 - 0.6	GR-Granular
NS-Nose Slope		L-Loam		SBK-Subangular Blocky
HS-Head Slope				ABK-Angular Blocky
CC-Concave Slope	III	SI-Silt	0.6 - 0.3	PL-Platy
CV-Convex Slope		SICL-Silty Clay Loam		PR-Prismatic
T-Terrace		CL-Clay Loam		
FP-Flood Plain		SCL-Sandy Clay Loam		
	IV	SC-Sandy Clay	0.4 - 0.1	
		SIC-Silty Clay		
		C-Clay		

Consistence Moist	Consistence Wet	*Mineralogy*
VFR-Very Friable	NS-Non-Sticky	SEXP-Slightly Expansive
FR-Friable	SS-Slightly Sticky	EXP-Expansive
FI-Firm	S-Sticky	
VFI-Very Firm	VS-Very Sticky	
EFI-Extremely Firm	NP-Non-Plastic	
	SP-Slightly Plastic	
	P-Plastic	
	VP-Very Plastic	

Sketch of Soil Evaluation Locations



Department of Environment, Health, and Natural Resources
Division of Environmental Health
On-site Wastewater Section

Sheet: 1 of 2
Property ID: 195-211-43
Lot #: 1
File #: 5786B
Code: 2

ACS

SOIL/SITE EVALUATION
for ON-SITE WASTEWATER SYSTEM

Owner: Audrey W. Mayhew
Applicant:
Address: 3362 Mayehw Forrest Lane, Charlotte, N. C., 28227
Date Evaluated: 11/22/2004
Proposed Facility: Residence
Design Flow (.1949): 480gpd
Property Size: .92a
Location of Site: Mayhew Country Drive
Property Recorded:
Water Supply: [ ] Public [x] Individual [x] Well [ ] Spring [ ] Other
Evaluation Method: [x] Auger Boring [ ] Pit [ ] Cut
Type of Wastewater: [x] Sewage [ ] Industrial Process [ ] Mixed

PROFILE #	.1940 Landscape Position/ Slope%	Horizon Depth (IN.)	SOIL MORPHOLOGY .1941 .1941 Structure/ Texture	.1941 Consistence Mineralogy	OTHER PROFILE FACTORS .1942 Soil Wetness/ Color	.1943 Soil Depth (IN.)	.1956 Sapro Class	.1944 Restr Horiz	Profile Class & LTAR
1	LS, 10	0-4	GR/CL	FR/SEXP/SS/SP	2.5Y7/1@24"	27+	N/A	NONE	US, IV
		4-23	SBK/C	FI/SEXP/S/P					
		23-27	SBK/CL	FR/SEXP/SS/SP					
2	"	0-6	GR/CL	"	"	32+	"	"	US
		6-15	SBK/C	FI/SEXP/S/P					
		15-32	ABK/C	VFI/EXP/VS/VP					
3	"	0-3	GR/CL	FR/SEXP/SS/SP	2.5Y7/1@32"	36+	"	"	"
		3-24	SBK/C	FI/SEXP/S/P					
		24-36	ABK/C	VFI/EXP/VS/VP					
4	"	0-4	GR/CL	FR/SEXP/SS/SP	2.5Y7/1@33"	37+	"	"	"
		4-27	SBK/C	FI/SEXP/S/P					
		27-37	ABK/C	VFI/EXP/VS/VP					
5	LS, 6	0-4	GR/CL	FR/SEXP/SS/SP	>39" TO SOIL WETNESS	39	"	"	PS, IV .225GPD/FT^2
		4-36	SBK/ABK/C	FI/SEXP/S/P					
		36-39	ABKPL/C	"					
6	"	0-3	GR/CL	FR/SEXP/SS/SP	>48" TO SOIL WETNESS	48	"	"	PS, IV .275GPD/FT^2
		3-48	SBK/ABK/C	FI/SEXP/S/P					
7	"	0-2	GR/CL	FR/SEXP/SS/SP	"	"	"	"	PS, IV .25GPD/FT^2
		2-48	SBK/ABK/C	FI/SEXP/S/P					

Description	Initial System	Repair System
Available Space (.1945)	PS	US
System Type(s)		
Site LTAR	.25GPD/FT^2	.25GPD/FT^2


Other Factors (.1946):
Site Classification (.1948): UNSUITABLE
Evaluated By: W. R. Marlin, LSS, 11/23/2004 W. R. Marlin
Others Present:

COMMENTS:
100% repair

Landscape Position	Group	Texture	.1955 LTAR	Structure
R-Ridge	I	S-Sand	1.2 - 0.8	SG-Single Grain
SS-Shoulder Slope		LS-Loamy Sand		M-Massive
LS-Linear Slope				CR-Crumb
FS-Food Slope	II	SL-Sandy Loam	0.8 - 0.6	GR-Granular
NS-Nose Slope		L-Loam		SBK-Subangular Blocky
HS-Head Slope				ABK-Angular Blocky
CC-Concave Slope	III	SI-Silt	0.6 - 0.3	PL-Platy
CV-Convex Slope		SICL-Silty Clay Loam		PR-Prismatic
T-Terrace		CL-Clay Loam		
FP-Flood Plain		SCL-Sandy Clay Loam		
	IV	SC-Sandy Clay	0.4 - 0.1	
		SIC-Silty Clay		
		C-Clay		

Consistence Moist	Consistence Wet	Mineralogy
VFR-Very Friable	NS-Non-Sticky	SEXP-Slightly Expansive
FR-Friable	SS-Slightly Sticky	EXP-Expansive
FI-Firm	S-Sticky	
VFI-Very Firm	VS-Very Sticky	
EFI-Extremely Firm	NP-Non-Plastic	
	SP-Slightly Plastic	
	P-Plastic	
	VP-Very Plastic	

Sketch of Soil Evaluation Locations



NEW OWNER

GWS – RES. APP 12/04

SEPTIC FEE:
DATE:
CRT:

PERMIT APPLICATION FOR A RESIDENTIAL SITE IMPROVEMENT PERMIT / CONSTRUCTION AUTHORIZATION FOR ON-SITE WASTEWATER SYSTEM NEW WELL INSTALLATION OR REPAIR OF EXISTING WELL MECKLENBURG COUNTY GROUNDWATER & WASTEWATER SERVICES

FILE # 5786B

ENTER
CRPU

SEPTIC / TYPE APPLICATION: ☐ NONE ☒ NEW SYSTEM EXISTING SYSTEM: ☐ EXPANSION/ALTERATION ☐ REPAIR

WELL / TYPE APPLICATION: ☒ NONE ☐ NEW WELL ☐ MAJOR REPAIR ☐ ABANDONMENT

JOB LOCATION INFORMATION:

TAX/PARCEL #: 19521143
STREET ADDRESS: 3321 Mintwood DR
CITY: MINT HILL
STATE: NC ZIP: 28227
SUBDIVISION OR MOBILE HOME PARK NAME: MAYhew Country Estates
LOT #: 1
TOWNSHIP:

☐ 0-MECKLENBURG ☐ 4-PINEVILLE
☐ 1-CHARLOTTE ☐ 5-MATTHEWS
☐ 2-DAVIDSON ☐ 6-HUNTERSVILLE
☐ 3-CORNELIUS ☒ 7-MINT HILL

BUILDING INFORMATION:

TYPE OF BUILDING:

☐ SINGLE MOBILE HOME (S) ☐ MODULAR HOME (M)
☐ DOUBLE WIDE (D) ☐ MULTIPLE FAMILY (U)
☒ HOUSE (H) ☐ OTHER

HEATED SQUARE FOOTAGE: 3014
NUMBER OF BEDROOMS: 4
NUMBER OF OCCUPANTS: 5

FOUNDATION FOR RESIDENCE:

☐ CONCRETE SLAB ☐ BASEMENT WITH PLUMBING
☒ CRAWLSPACE ☐ BASEMENT WITH NO PLUMBING

IF PLANNING TO EXPAND/ALTER THE EXISTING SYSTEM INDICATE THE FOLLOWING CHANGES:
NUMBER OF BEDROOMS TO BE ADDED: NUMBER OF ADDITIONAL OCCUPANTS IN THE RESIDENCE:
WILL THERE BE A HOME BUSINESS IN THE RESIDENCE? ☐ YES ☐ NO TYPE:

WATER SUPPLY:

☐ MUNICIPAL (M) ☒ PUBLIC (C) ☐ PRIVATE WELL (P) ☐ SHARED WELL (S) ☐ OTHER 'SPRINGS' (O)

PROPOSED USE OF WELL: ☐ N/A ☐ IRRIGATION ☐ POTABLE ☐ GEOTHERMAL ☐ OTHER

ARE ANY OF THE FOLLOWING LOCATED ON THE PROPERTY? IF SO, PLEASE SHOW LOCATION ON SITE PLAN/PLAT.

BURIED CABLES, LANDFILLS, STUMPHOLES	☐ YES	☒ NO	WELLS, SPRINGS, OR WATER LINES	☐ YES	☒ NO
EXISTING WASTEWATER SYSTEMS	☐ YES	☒ NO	DESIGNATED WETLANDS	☐ YES	☒ NO
EASEMENTS OR RIGHT-OF-WAYS	☐ YES	☒ NO	GRADING/SOIL REMOVAL PERFORMED	☐ YES	☒ NO

PROPERTY OWNER:

NAME: LISA L. Macellan
ADDRESS: 7535 ELWOOD DR
CITY: CHARLOTTE
STATE: NC ZIP: 28227
HOME PHONE: 704-535-8559 WORK PHONE: 704-897-1168
MOBILE PHONE: 704-746-4466 FAX: 704-897-1128

LEGAL AGENT FOR PROPERTY OWNER, IF APPLICABLE:

NAME:
ADDRESS:
CITY:
STATE: ZIP:
HOME PHONE: WORK PHONE:
MOBILE PHONE: FAX:

WHAT DATE WAS THE PROPERTY ORIGINALLY DEEDED AND RECORDED? 8/2005
WHAT IS THE ANTICIPATED CLOSING DATE FOR THIS PROPERTY? 3/1/2005 - Construction of home

*An Improvement Permit is subject to suspension or revocation if site plans or the intended use change or if information submitted in this application is falsified or changed. The undersigned, owner, or legal agent for the owner, of the property described above as the "Job Location" has read the foregoing application, acknowledges that the contents of same are true, and authorizes the Mecklenburg County Health Department to enter onto the property for the purpose of processing this request.

Lisa L. Macellan 11/4/05
Owner's/Agent's Signature Date

NORTH CAROLINA DEPARTMENT OF
ENVIRONMENT & NATURAL RESOURCES DIVISION
OF ENVIRONMENTAL HEALTH ON-SITE
WASTEWATER SECTION

*A Well Permit is subject to suspension or revocation if site plans or the intended use change or if information submitted in this application is falsified or changed. The undersigned, owner, or legal agent for the owner, of the property described above as the "Job Location" has read the foregoing application, acknowledges that the contents of same are true, and authorizes the Mecklenburg County Health Department to enter onto the property for the purpose of processing this request.

Owner's/Agent's Signature Date

MECKLENBURG COUNTY HEALTH DEPARTMENT
GROUNDWATER & WASTEWATER SERVICES
700 N. TRYON ST., SUITE 211
CHARLOTTE, NC 28202
704-336-5103 / FAX: 704-336-6894

Nov 04 2005 4:14PM LUESR NORTH 704 432 2523 p.2

FEE: 200
DATE: 11/18/04
Check 3111 OKA

APPLICATION FOR IMPROVEMENT PERMIT FOR RESIDENTIAL SITE INDIVIDUAL WATER AND WASTEWATER SYSTEMS PROGRAM

[ ] CRT

TYPE APPLICATION: ✓ NEW SYSTEM ___ EXPANSION/ ALTERATION OF EXISTING SYSTEM ___ REPAIR OF EXISTING SYSTEM

NORTH CAROLINA
DEPARTMENT OF ENVIRONMENT,
HEALTH, AND NATURAL RESOURCES
DIVISION OF ENVIRONMENTAL HEALTH
ON-SITE WASTEWATER SECTION

FILE #: 57866

PROPERTY INFORMATION (FROM ENGINEERING FORM) FOR JOB LOCATION:

TAX/PARCEL NUMBER: 195-211-39PO

STREET ADDRESS: Mayhew Country Drive

SUBDIVISION OR MOBILE HOME PARK NAME: Mayhew Country Estates

LOT NUMBER: 1

TYPE OF BUILDING (CHECK ONE):

___ SINGLE MOBILE HOME(S)
___ DOUBLE WIDE (D)
X HOUSE (H)
___ MODULAR HOME (M)
___ MULTIPLE FAMILY (U)
___ OTHER (O)

TOWNSHIP (CHECK ONE):

✓ 0 MECKLENBURG
___ 1 CHARLOTTE
___ 2 DAVIDSON
___ 3 CORNELIUS
___ 4 PINEVILLE
___ 5 MATTHEWS
___ 6 HUNTERSVILLE
X 7 MINT HILL

HEATED SQUARE FOOTAGE:

NUMBER OF BEDROOMS:

NUMBER OF OCCUPANTS:

CLOSING DATE

FOUNDATION FOR RESIDENCE:

___ WITHOUT BASEMENT
___ ON SLAB
___ CRAWL SPACE
___ WITH BASEMENT /PLUMBING
___ WITH BASEMENT /NO PLUMBING

IF EXPANSION/ALTERATION OF EXISTING SYSTEM, DESCRIBE THE PROPOSED BUILDING ADDITION:

WILL THERE BE A HOME BUSINESS IN THE RESIDENCE: ___ YES X NO TYPE:

WATER SUPPLY (CHECK ONE): Well and City water

___ COMMUNITY (C)
___ SHARED WELL (S)
___ MUNICIPAL (M)
___ OTHER 'SPRINGS' (O)
X PRIVATE WELL (P)

IF ANY OF THE FOLLOWING ARE LOCATED ON THE PROPERTY, PLEASE SHOW LOCATION ON PLAT:

BURIED CABLES, LANDFILLS, STUMPHOLES ✓ YES ___ NO
EXISTING WASTEWATER SYSTEMS ___ YES ✓ NO
EASTMENTS OR RIGHT-OF-WAYS ✓ YES ___ NO
WELL, SPRINGS OR WATERLINES ___ YES ✓ NO
DESIGNATED WETLANDS ? ✓ YES ___ NO

PROPERTY OWNER:	LEGAL AGENT FOR PROPERTY OWNER, IF APPLICABLE:
NAME: (LAST) MAYHEW (FIRST) AUDREY (MI) W	NAME: (LAST) (FIRST) (MI)
ADDRESS:	DAYTIME PHONE: ( ) -
CITY: Charlotte STATE: N.C ZIP:	
DAYTIME PHONE: 704 540 3241	

WHAT DATE WAS THE PROPERTY ORIGINALLY DEEDED AND RECORDED? 1965

An Improvement Permit is subject to suspension or revocation if site plans or the intended use change or if information submitted in this application is falsified or changed. The undersigned, owner, or legal agent for the owner, of the property described above as the "Job Location" has read the foregoing application, acknowledges that the contents of same are true, and authorizes agents of the Mecklenburg County Health Department to enter onto the property for the purpose of processing this request.

SIGNED: Audrey Mayhew DATE: 11-10-04

MECKLENBURG COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
c/o HAL MARSHALL CTR., SUITE 211, 700 N. TRYON ST., CHARLOTTE, N.C. 28202., (704) 336-5102

We have water as well

November 11, 2004

I am applying to Mecklenburg County for a soil test for lot 1 of Mayhew Country Estates. I have this lot for sale and want to be sure it perks when I take an application to sell it. I recently sold lot 4 and found out three weeks into the sale it would not perk. I don't want this to happen again. I don't plan to build on this lot. I have enclosed a map of the subdivision and a survey of the lot. At my request he has shown out many square feet I can put on this lot providing it does perk. The lot fronts on Mayhew Country Drive. I hope I have included every thing you need. You can reach me at 704 545-3741. I have enclosed a check for $200.00.

Thank you

Audrey mayhew


Audrey mayhew

CURVE TABLE				
CURVE	LENGTH	RADIUS	BEARING	CHORD
C1	28.28'	20.00'	N 15°40'29" E	25.98'

File # 5786B

TC # 195-211-39PO

Parcel 195-211-39



60' Public R/W Mayhew Country Drive

Surveyor's house drawn in largest building possible



NOTE:
ALL CORNERS ARE I.PIN(F) UNLESS OTHERWISE NOTED.

NOTE:
ALL DISTANCES ARE HORIZONAL DISTANCES UNLESS OTHERWISE NOTED.

NOTE:
AREA BY COORDINATE COMPUTATION.

NOTE:
PROPERTY SUBJECT TO ANY VALID & ENFORCEABLE EASEMENTS, RESTRICTIONS & RIGHTS OF WAY OF RECORD.

SUBJECT PROPERTY IS NOT LOCATED IN A SPECIAL FLOOD HAZARD AREA AS DETERMINED BY FLOOD INSURANCE RATE MAP.

NOTE:
THIS PLAT IS OF A SURVEY OF AN EXISTING PARCEL or PARCELS OF LAND.

Location Map
(Not To Scale)

Tax Parcel:

E.C. = 1' : 10,000' +

Deed Ref:
Map Book: 32 / 156

Plot Plan
For

Audrey Mayhew

Lot 1, Mayhew Country Estates, Map 1

Mecklenburg County
Mint Hill, N.C.

Drawing No. 355-04

Scale: 1" = 50'

July 2, 2004